



Brian J. Wendling
Public Works Commissioner
Governmental Center
111 S. Michigan Ave., Suite 103
Saginaw, MI 48602
Phone 989-790-5258
Fax 989-790-5259

SAGINAW COUNTY PUBLIC WORKS COMMISSIONER

SAVAGE DRAIN

NOTICE OF LETTING

NOTICE OF LETTING

DATE: May 24, 2023
TIME: 10:00 a.m.
LOCATION: Spicer Group, Inc.
230 S. Washington Avenue
Saginaw, MI 48607
QUESTIONS: (989) 790-5258

The Saginaw County Public Works Commissioner will meet on the above date, time and location to receive construction bids for the Savage Drain. Bids will then be opened and publicly announced.

The Savage Drain project will be let in 2 sections as follows, each section having the length, average depth and width as set forth:

Said Drain is an existing open channel drain with dikes and flapgates at the outlet for flood protection. Project includes reconstruction of dikes along approximately 1 mile of drain and replacement of the flapgate structure. This Notice of Letting, the plans, specifications, and bid proposal shall be considered a part of the contract. The following items will be required, and a contract let for same:

DIVISION I - OPTION A - OUTLET STRUCTURE

SAVAGE DRAIN OUTLET

300	Lin. Ft.	Dike and Channel Reconstruction (Misteguay Creek)
3	Each	8' x 8' Flap Gate (Fontaine)
2	Each	4' x 3.5' Flap Gate (Fontaine)
1	Lump Sum	Concrete Outlet Structure, Complete (Includes Apron, Footing, Wall, Walkway)
1	Lump Sum	Temporary Dewatering and Cofferdams
1	Lump Sum	Demolition (Existing Outlet Structure)
1	Lump Sum	Sitework and Grading
150	Cu. Yds.	Subgrade Undercut
1,400	Sq. Yds.	Miscellaneous Riprap

OPEN CHANNEL CONSTRUCTION

300	Lin. Ft.	Dike and Channel Reconstruction - Left Side (Sta. 0+00 to 3+00)
300	Lin. Ft.	Dike and Channel Reconstruction - Right Side (Sta. 0+00 to 3+00)
1	Lump Sum	Sediment Sump
1	Lump Sum	Site Clearing - Both Sides

SOIL EROSION AND SEDIMENT CONTROL

50	Lin. Ft.	Plain Riprap Toe of Slope
50	Lin. Ft.	Plain Riprap Spillway
1	Lump Sum	Seeding, Fertilizing, and Blown Straw Mulch - On Dike
1	Lump Sum	Cleanup and Restoration

DIVISION I - OPTION B - OUTLET STRUCTURE

SAVAGE DRAIN OUTLET

300	Lin. Ft.	Dike and Channel Reconstruction (Misteguay Creek)
3	Each	8' x 8' Flap Gate (Fontaine)
2	Each	48" Flap Gate (Fontaine)
210	Lin. Ft.	8' Rise x 8' Span Concrete Box Culvert
128	Lin. Ft.	48" RCP (C-76, CL IV)
1	Lump Sum	Concrete Headwall and Wingwalls, Complete (Includes Apron and Footing)
1	Lump Sum	Temporary Dewatering and Cofferdams
1	Lump Sum	Demolition (Existing Outlet Structure)
1	Lump Sum	Sitework and Grading
200	Cu. Yds.	Subgrade Undercut
1,000	Sq. Yds.	Miscellaneous Riprap

OPEN CHANNEL CONSTRUCTION

300	Lin. Ft.	Dike and Channel Reconstruction - Left Side (Sta. 0+00 to 3+00)
300	Lin. Ft.	Dike and Channel Reconstruction - Right Side (Sta. 0+00 to 3+00)
1	Lump Sum	Sediment Sump
1	Lump Sum	Site Clearing - Both Sides

SOIL EROSION AND SEDIMENT CONTROL

50	Lin. Ft.	Plain Riprap Toe of Slope
50	Lin. Ft.	Plain Riprap Spillway
1	Lump Sum	Seeding, Fertilizing, and Blown Straw Mulch - On Dike
1	Lump Sum	Cleanup and Restoration

DIVISION II - DIKE RECONSTRUCTION

OPEN CHANNEL CONSTRUCTION

5,060	Lin. Ft.	Dike and Channel Reconstruction - Left Side (Sta. 3+00 to 53+60)
5,060	Lin. Ft.	Dike and Channel Reconstruction - Right Side (Sta. 3+00 to 53+60)
1	Lump Sum	Site Clearing - Both Sides

BLAINE PUMP STATION (STA. 21+50 - RIGHT SIDE)

12	Lin. Ft.	6' Dia. Manhole Crock (Paid Per Vertical Lin. Ft.)
5	Lin. Ft.	48" RCP (C-76, CL III)
1	Each	48" RCP Flared End Section
1	Lump Sum	Pump Removal and Reinstallation (Includes Fabrication for Reinstallation)
64	Lin. Ft.	36" RCP (C-76, CL IV)
1	Each	36" RCP Flared End Section
1	Each	Precast Concrete Headwall (w/out Baffle)

1	Each	36" Flapgate (Fontaine)
1	Lump Sum	Electrical, Complete
1	Lump Sum	Demolition
1	Lump Sum	Grading and Sitework

SOIL EROSION AND SEDIMENT CONTROL

200	Sq. Yds.	Miscellaneous Riprap
200	Lin. Ft.	Plain Riprap Toe of Slope
200	Lin. Ft.	Plain Riprap Spillway
1	Lump Sum	Seeding, Fertilizing, and Blown Straw Mulch - On Dike
1	Lump Sum	Cleanup and Restoration

Field Tiles

3	Each	Precast Concrete Headwall (Sized for 8" Tile and Flapgate)
180	Lin. Ft.	8" Tile Outlet Replacement (PVC, SDR-26)
3	Each	Flap Gate (Fontaine - Flatback) (Size Required for 8" Tile)
100	Lin. Ft.	12" Header Tile Relocation (Single Wall, Heavy Duty)
100	Lin. Ft.	10" Header Tile Relocation (Single Wall, Heavy Duty)
100	Lin. Ft.	8" Header Tile Relocation (Single Wall, Heavy Duty)
3	Each	Plain Riprap Splash Pad

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at Spicer Group, 230 S. Washington Ave., Saginaw, MI (Luke O'Brien, 989-280-2109) and available to interested parties. Bids will be made and received in accordance with these documents. Bidding Documents, including plans and specifications, may be examined at the following locations:

Saginaw County Public Works Commissioner: Digital documents on website at no charge

<http://www.saginawcounty.com/departments/public-works-drain-office/current-projects/>


Copies of Bidding Documents may only be obtained upon payment of a **\$100.00 non-refundable** deposit. (Contact Angie McCullen, 989-921-5538).

A security deposit drawn payable to the **Savage Drain Drainage District** in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

A **mandatory pre-bid conference** will be held at **9:00 a.m.** on the **3rd day of May, 2023**, at the office of Spicer Group, Inc., 230 S. Washington Avenue, Saginaw, Michigan 48607. It is a requirement that any prospective General Contractor bidding attend this meeting. Representatives of the Drainage District and Spicer Group, Inc. will be present to discuss the project. Attendance is required for sealed bids to be accepted. Spicer Group, Inc. will transmit to all prospective bidders of record an Addendum as Spicer Group, Inc. considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be legally effective.

The Contract will be awarded to the lowest responsive and responsible bidder giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

Dated: April 26, 2023



Brian J. Wendling
Saginaw County Public Works Commissioner