

MARSH CREEK #2 DRAIN

SAGINAW COUNTY PUBLIC WORKS COMMISSIONER - BRIAN J. WENDLING



PLAN INDEX					
FILE NO.	DESCRIPTION	NO.			
DR-4707-01	COVER SHEET	1			
DR-4707-02	CONTACTS, GENERAL NOTES, LINE TYPE LEGEND	2			
DR-4707-03	SOIL EROSION AND SEDIMENTATION CONTROL PLAN	3			
DR-4707-04	DRAINAGE DISTRICT MAP	4			
DR-4707-05	PLAN AND PROFILE - STA 0+00 TO STA 50+00	5			
DR-4707-06	PLAN AND PROFILE - STA 50+00 TO STA 100+00	6			
DR-4707-07	PLAN AND PROFILE - STA 100+00 TO STA 150+00	7			
DR-4707-08	PLAN AND PROFILE - STA 150+00 TO STA 200+00	8			
DR-4707-09	PLAN AND PROFILE - STA 200+00 TO STA 250+00	9			
DR-4707-10	PLAN AND PROFILE - STA 250+00 TO STA 300+00	10			
DR-4707-11	PLAN AND PROFILE - STA 300+00 TO STA 350+00	11			
DR-4707-12	PLAN AND PROFILE - STA 350+00 TO STA 400+00	12			
DR-4707-13	PLAN AND PROFILE - STA 400+00 TO STA 450+00	13			
DR-4707-14	PLAN AND PROFILE - STA 450+00 TO STA 499+70	14			
DR-4707-15	CROSS SECTIONS - STA 6+63 TO STA 70+04	15			
DR-4707-16	CROSS SECTIONS - STA 75+15 TO STA 130+73	16			
DR-4707-17	CROSS SECTIONS - STA 139+98 TO STA 196+24	17			
DR-4707-18	CROSS SECTIONS - STA 201+28 TO STA 265+19	18			
DR-4707-19	CROSS SECTIONS - STA 269+94 TO STA 337+20	19			
DR-4707-20	CROSS SECTIONS - STA 342+08 TO STA 409+67	20			
DR-4707-21	CROSS SECTIONS - STA 417+80 TO STA 496+19	21			
DR-4707-22	STANDARD DETAILS	22			
DR-4707-23	STANDARD DETAILS	23			



BY MARK REVISIONS DATE

THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.

MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN

COVER SHEET



SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

 DE. BY:
 POC/CDV
 CH. BY:
 CDV
 PROJECT NO.

 DR. BY:
 MJC
 APP. BY:
 NDC
 135292SG2023

 STDS.
 SHEET
 01
 OF
 23
 DR

 DATE
 DECEMBER, 2024
SCALE
 FILE NO.
DR-4707-01
 01

CHAD SENSABAIJOH/12/8/2024

GENERAL NOTES

NO WORK SHALL BE PERFORMED BEFORE 7:00 AM OR AFTER 7:00 PM MONDAY THROUGH SATURDAY. NO WORK SHALL HAPPEN ON SUNDAYS OR HOLIDAYS, UNLESS AUTHORIZED BY THE OWNER.

CONTRACTOR SHALL NOTIFY ENGINEER 48 HOURS PRIOR TO START OF CONSTRUCTION, CONSTRUCTION STAKING AND INSPECTION.

CONTRACTOR SHALL MAINTAIN ACCESS FOR MAIL DELIVERY AND GARBAGE PICKUP AT ALL PARCELS. IF THESE SERVICES CANNOT BE PERFORMED, CONTRACTOR IS RESPONSIBLE FOR TAKING THE NECESSARY MEASURES TO CARRY THEM OUT.

COORDINATE DRIVE CLOSURES AND MAIL BOX RELOCATION WITH LANDOWNERS A MINIMUM OF ONE DAY IN ADVANCE.

CONTRACTOR TO PROVIDE DUST CONTROL AND SWEEP ROADS DAILY.

ALL EXCAVATED MATERIAL NOT TO BE REUSED OR DISPOSED OF ON SITE SHALL BE REMOVED FROM SITE. THE CONTRACTOR IS RESPONSIBLE FOR DISPOSING OF MATERIALS ACCORDING TO LOCAL AND STATE REQUIREMENTS.

UNDERGROUND UTILITIES/MISS DIG

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174, 2013, THE CONTRACTOR SHALL DIAL 1-800-482-7171 OR 811 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS, PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.

THE EXISTING UTILITIES ON THESE DRAWINGS HAVE BEEN SHOWN ACCORDING TO THE BEST AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND SHALL NOTIFY THE ENGINEER AS TO WHERE POSSIBLE CONFLICT EXISTS.

ALL CONSTRUCTION UNDER EXISTING UTILITIES, INCLUDING HOUSE SERVICES, SHALL BE COMPLETELY BACKFILLED WITH SAND, IN 12" LAYERS, AND COMPACTED TO NOT LESS THAN 95% OF THE MAXIMUM UNIT WEIGHT.

ANY UTILITIES ENCOUNTERED DURING CONSTRUCTION SHALL BE SUPPORTED, PER THE SPECIFICATIONS OF THE INDIVIDUAL UTILITY COMPANY CLAIMING OWNERSHIP OF THE UTILITY.

SOIL EROSION AND SEDIMENTATION CONTROL MEASURES

APPROPRIATE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO EARTH-DISTURBING ACTIVITIES. PLACE TURF ESTABLISHMENT ITEMS AS SOON AS POSSIBLE ON POTENTIAL ERODABLE SLOPES AS DIRECTED BY OWNER. CRITICAL DITCH GRADES SHALL BE PROTECTED WITH EITHER SOD, SEED/MULCH, OR SEED/MULCH BLANKET AS DIRECTED BY OWNER.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT SOIL EROSION AND SEDIMENTATION CONTROL MEASURES ARE IN PLACE AND MAINTAINED UNTIL THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED. MEASURES SHALL ONLY BE PAID FOR ONCE.

ALL CATCHBASINS AND SEDIMENTATION TRAPS/BASINS SHALL BE CLEANED OUT UPON COMPLETION OF THE PROJECT.

CONTRACTOR SHALL CONFORM TO SOIL EROSION AND SEDIMENTATION CONTROL ACT, PART 91 OF ACT 451 OF 1994.

PROPERTY OWNERS

PROPERTY OWNERS' NAMES, WHERE SHOWN, ARE FOR INFORMATION ONLY, AND THEIR ACCURACY IS NOT GUARANTEED.

ADJUSTING MONUMENT BOXES

ALL GOVERNMENT CORNERS ON THIS PROJECT SHALL BE PRESERVED, WHETHER SHOWN OR NOT. IT MAY BE NECESSARY TO PLACE OR ADJUST MONUMENT BOXES, AS REQUIRED.

TRAFFIC

THE CONTRACTOR SHALL MAINTAIN LOCAL TRAFFIC AT ALL TIMES. SIGNAGE MUST BE IN ACCORDANCE WITH THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SHALL BE COORDINATED WITH THE ENGINEER AND GOVERNING ROAD AGENCY. PERMITS MAY BE REQUIRED.

PERMITS

PRIOR TO COMMENCING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS REQUIRED BY THE APPROPRIATE AGENCIES.

CONSTRUCTION PROCEDURES SHALL CONFORM TO THE REQUIREMENTS OF THE APPROPRIATE AGENCIES.

<u>CONTACTS</u>	
SAGINAW COUNTY PUBLIC WORKS COMMISSIONER ATT: BRIAN J. WENDLING 111 S. MICHIGAN AVENUE SAGINAW, MI 48602 PHONE: (989) 790-5258	OWNER
SPICER GROUP ATT: CHRISTIAN VALESANO, P.E. 230 S. WASHINGTON AVENUE SAGINAW, MI 48607 PHONE: (906) 284-1862	ENGINEER
DOW CHEMICAL ATT: ROBERT BEAUVAIS 28550 CABOT DRIVE, SUITE 500 NOVI, MI 48377 PHONE: (248) 639-7093	BRINE
CONSUMERS ENERGY ATT: BENJAMIN LEWIS 2400 WEISS STREET SAGINAW, MI 48602 PHONE: (989) 791-5918	GAS
CONSUMERS ENERGY ATT: VIRGIE DOWNS 2400 WEISS STREET SAGINAW, MI 48602 PHONE: (989) 791-5353	ELECTRICAL
AT&T ATT: MATTHEW FARNEY 54 N. MILL STREET PONTIAC, MI 48342 PHONE: (734) 516-7930	TELEPHONE
CHARTER COMMUNICATIONS ATT: DAN BIELACZYC 1480 S. VALLEY CENTER BAY CITY, MI 48706 PHONE: (231) 941-3819	CABLE

CABLE

FRONTIER/VERIZON

ATT: HUNTER TAPHOUSE

PHONE: (517) 442-3643

EMAIL: HUNTER.TAPHOUSE@ATCOTELECOM.COM

GENERAL NOTES CONT.

ALL WORK SHALL BE CONFINED TO THE RIGHT-OF-WAY OR CONSTRUCTION LIMITS SHOWN ON THE PLANS. ANY WORK OUTSIDE OF THESE LIMITS SHALL BE AGREED TO BY THE CONTRACTOR AND THE LANDOWNER IN WRITING.

RESTORE ALL LAWN AREAS PER SPECIFICATIONS AND PLANS.

CONTRACTOR TO RESTORE INCIDENTAL DAMAGES ON THE PROJECT AS DIRECTED BY OWNER AND ENGINEER AT THE CONTRACTOR'S EXPENSE.

ALL DRAIN SIDE SLOPES SHALL BE 2H:1V OR FLATTER, UNLESS SPECIFIED OTHERWISE.

THE WORDS "RIGHT SIDE" OR "LEFT SIDE" IMPLY A REFERENCE TO THE DRAIN FACING UPSTREAM.

REMOVE EXISTING FENCES, LANDSCAPING, AND OTHER STRUCTURES IN RIGHT-OF-WAY OR CONSTRUCTION LIMITS AS-NEEDED FOR CONSTRUCTION. COST TO BE INCLUDED IN SITE CLEARING.

REINSTALLATION OF FENCES MUST BE COORDINATED WITH THE LANDOWNER AT THE LANDOWNER'S EXPENSE, UNLESS STATED OTHERWISE IN THE PLANS. ALL SPRINKLER SYSTEMS DAMAGED SHALL BE REPAIRED BY CONTRACTOR. COST OF THE PAY ITEM BEING INSTALLED,

UNLESS OTHERWISE NOTED. CONTRACTOR TO CLEAR TREES WITHIN THE RIGHT-OF-WAY OR CONSTRUCTION LIMITS AS NECESSARY TO CONSTRUCT

PROJECT AND LEVEL SPOILS AS SHOWN IN DETAILS. COORDINATE REMOVALS WITH THE ENGINEER/LANDOWNER.

ROADS, DRIVEWAYS AND SIDEWALKS ALL JOINTS AT INTERSECTION APPROACHES AND DRIVEWAYS SHALL BE SAW-CUT WITH BUTT-JOINTS.

FOR OPEN CUT PAVEMENT REMOVAL, CONTRACTOR SHALL SAW CUT THE EXISTING PAVEMENT FULL DEPTH PRIOR TO

ALL DRIVING SURFACES ARE TO BE RESTORED TO IN-KIND DEPTH AND MATERIAL, UNLESS OTHERWISE SPECIFIED ON THE PLANS.

PROTECT ALL ROADS NOT SPECIFIED TO BE REMOVED DURING CONSTRUCTION. REPAIR ANY UNAUTHORIZED DAMAGE AT CONTRACTOR'S EXPENSE.

BROKEN CONCRETE AND DEBRIS SHALL BE CONSIDERED WASTE AND SHALL BE DISPOSED OF BY THE CONTRACTOR OFF-SITE. COST SHALL BE INCLUDED IN THE OTHER PAY ITEMS OF THE PROJECT.

MATCH EXISTING TYPE FOR CONCRETE CURB AND GUTTER RESTORATION.

CONTRACTOR SHALL REMOVE AND REPLACE ALL STREET AND TRAFFIC SIGNAGE AS NECESSARY FOR CONSTRUCTION. ALL COST SHALL BE INCLUDED IN THE BID PRICE FOR SITE CLEARING.

CONTRACTOR SHALL COORDINATE LOCATION OF ANY ACCESS ROADS WITH THE LANDOWNER AND THE ENGINEER. ANY ACCESS ROAD SHALL BE REPAIRED TO THE OWNER'S SATISFACTION.

ALL WORK WITHIN THE ROAD RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE CURRENT STANDARDS AND GENERAL SPECIFICATIONS OF THE AGENCY WITH JURISDICTION OVER THE ROAD.

CONTRACTOR SHALL REMOVE AND TEMPORARILY RELOCATE ALL EXISTING MAIL BOXES AS NEEDED FOR CONSTRUCTION. COSTS TO BE INCLUDED IN THE UNIT PRICE BID FOR SITE CLEARING.

ALL TEMPORARILY RELOCATED MAIL BOXES, STREET AND TRAFFIC SIGNS TO BE REINSTALLED TO ORIGINAL LOCATIONS AS CONSTRUCTION ALLOWS. COSTS TO BE INCLUDED IN THE UNIT PRICE BID FOR CLEANUP AND RESTORATION.

UTILITIES

UTILITIES LOCATED IN THE ROAD AND DRAIN RIGHTS-OF-WAY WILL BE RELOCATED BY OTHERS, UNLESS OTHERWISE NOTED ON THE PLANS.

THE PUBLIC WORKS COMMISSIONER'S MINIMUM CLEARANCE STANDARDS SHALL BE MET WHENEVER RELOCATING EXISTING UTILITIES WITHIN THE DRAIN RIGHT-OF-WAY.

ALL WATER VALVE BOXES SHALL BE ADJUSTED TO FINISHED GRADE. COST SHALL BE INCLUDED IN THE PAY ITEM BEING INSTALLED.

ANY UTILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

ALL MANHOLE RIMS IN ROADWAYS AND DRIVES SHALL BE ADJUSTED PRIOR TO FINAL PAVING TO BE FLUSH WITH FINISHED GRADE.

GRADING AROUND MANHOLES/CATCHBASINS, FLARED END SECTIONS, AND OTHER INLETS SHALL BE SMOOTH AND SHAPED TO PROVIDE POSITIVE DRAINAGE INTO THE INLETS.

DEMOLISH EXISTING STRUCTURE(S) AND DISPOSE OF IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS. COST TO BE INCLUDED WITH THE ITEM BEING INSTALLED AS DIRECTED BY OWNER/ENGINEER.

CONTRACTOR SHALL CONNECT ANY AND ALL FIELD TILE OUTLETS AND OTHER STORM LEADS TO PROPOSED STORM SEWER WITH PREMANUFACTURED TEES, WYES, GASKETS, SEALS, COUPLERS, BOOTS, ETC. PER SPECIFICATIONS.

SOIL EROSION SEDIMENT CONTROL

ALL RIPRAP MATERIAL SHALL BE APPROVED BY THE ENGINEER. OWNER AND ENGINEER RESERVES THE RIGHT TO REJECT ANY AND ALL RIPRAP.

CONTRACTOR SHALL FINISH GRADE, SEED, FERTILIZE, AND MULCH DAILY ON ALL DISTURBED AREAS AS DESCRIBED IN THE SPECIFICATIONS.

PROJECT NOTES

- 1. ALL MAINTENANCE ACCESS CULVERTS MATERIAL SHALL BE EITHER RCP(C-76, CL-III), ADS HP STORM, OR ALUMINIZED CORRUGATED METAL PIPE (12 GA).
- 2. LOG JAM LOCATIONS SHOWN ARE APPROXIMATED BASED ON FIELD REVIEW IN DECEMBER 2023. CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL LOG JAMS PRESENT AT THE TIME OF CONSTRUCTION, REGARDLESS OF CHANGE IN FIELD CONDITIONS SINCE INITIAL FIELD REVIEW.

ABBREVIATIONS

BC = BACK OF CURB BM = BENCH MARK CB = CATCH BASIN C/C = CENTER TO CENTER CJ = CONSTRUCTION JOINT CL = CENTERLINE CMP = CORRUGATED METAL PIPE CONC = CONCRETE CORR = CORRUGATED CSP = CORRUGATED STEEL PIPE DI = DUCTILE IRON PIPE EF = EACH FACE ELEC = ELECTRIC EL OR ELEV = ELEVATION EOM = EDGE OF METAL EOP = EDGE OF PAVEMENT EQ/SP = EQUALLY SPACED ESMT = EASEMENT EW = EACH WAY EX OR EXIST = EXISTING FES = FLARED END SECTION FF = FINISH FLOOR FG = FINISH GROUND FL = FLOW LINE FS = FINISH SURFACE FT = FEET GALV = GALVANIZED G = GUTTERGA = GAUGE HDG = HOT DIP GALVANIZED HDPE = HIGH DENSITY POLYETHYLENE HMA = HOT MIX ASPHALT HOR = HORIZONTAL HP = HIGH POINT HYD = HYDRANT OC = ON CENTER OH = OVERHEAD

INV = INVERT LP = LOW POINT MH = MANHOLE MIN = MINIMUMMON = MONUMENT NFL = NOT FIELD LOCATED NTS = NOT TO SCALE PROP = PROPOSED PVC = POLYVINYL CHLORIDE RCP = REINFORCED CONCRETE PIPE ROW = RIGHT OF WAY SAN = SANITARY SB = SOIL BORING

SS = STAINLESS STEEL STA = STATION STM = STORM SWR = SEWER T/B = TOP AND BOTTOM TC = TOP OF CURB TOB = TOP OF BANK TOS = TOE OF SLOPE

TELE = TELEPHONE TRW = TOP OF RETAINING WALL TW = TOP OF WALK UG = UNDERGROUND UNO = UNLESS NOTED OTHERWISE VERT = VERTICAL WM = WATERMAIN

WSEL = WATER SURFACE ELEVATION

LINE TYPE LEGEND

- EXISTING ROAD CENTERLINE ______ - EXISTING WATERMAIN - EXISTING SANITARY SEWER OR FORCEMAIN ______ - EXISTING STORM SEWER __ __ __ __ - EXISTING TELEPHONE CABLE - EXISTING GAS MAIN ——G———G——— - EXISTING ELECTRIC - EXISTING DRAINS (OTHER) - PROPOSED UTILITY - EXISTING CURB & GUTTER - PROPOSED CURB & GUTTER — x — x — x — - FENCE LINE - OVERHEAD UTILITY ____//____//__ - RAILROAD TRACKS - STATION LINE - LIMITS OF RIGHT OF WAY - EASEMENT - SILT FENCE - REVERSE PAN CURB & GUTTER - TREE LINE - EXISTING CONTOURS - PROPOSED CONTOURS

SYMBOL LEGEND **EXISTING SYMBOLS**

- BARRIER FREE PARKING O - MANHOLE ∅ - CATCH BASIN - SPRINKLER a - RAILROAD SIGNAL Y - FIRE HYDRANT - SATELLITE DISH ⊕ - GAS VALVE - AIR CONDITIONING UNIT ⊗ - WATER VALVE • SOIL BORING □ - TELEPHONE PEDESTAL ● - POWER POLE - CONTROL POINT Ø - TELEPHONE POLE + - BENCH MARK ∵ - LIGHT POLE • - SET 1/2" IRON ROD ← ○ - GUY ANCHOR AND POLE • - 1/4 SECTION CORNER - MAIL BOX —√— - BREAK IN LINE ■ - WATER METER - - EXISTING SIGN-1 POST ① - TELEPHONE MANHOLE - - EXISTING SIGN-2 POST © - ELECTRIC MANHOLE 凡 - STUMP (C)M.W. - MONITORING WELL 业 - WETLANDS - PINE - TRANSFORMER ₫ - BUSH ■ - ELECTRICAL PEDESTAL

PROPOSED SYMBOLS

· - TREE

O - MANHOLE - CATCHBASIN

Y - FIRE HYDRANT

 WATER VALVE - BARRIER FREE PARKING

- LIGHT POLES → - DRAINAGE FLOW

- SPOT ELEVATION LABELS G = GUTTERTW = WALKTC = TOP OF CURB

FS = FINISH SURFACE

PROJECT DATUM STATE PLANE SOUTH MI '83 2113 HORIZONTAL. VERTICAL: NORTH AMERICAN VERTICAL DATUM '88 BY MARK REVISIONS THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.

> MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN

CONTACTS, GENERAL NOTES, LINE TYPE LEGEND



230 S. Washington Ave Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

PROJECT NO.

DR. BY: MJC APP. BY: NDC 135292SG2023 SHEET **02** OF **23** FILE NO. DATE DECEMBER, 2024 DR-4707-02 SCALE NOT TO SCALE

DE. BY: POC/CDV CH. BY: CDV

ROUTINE MAINTENANCE ACTIVITIES

KEY	BEST MANAGEMENT PRACTICE	SESC PLAN
А	Debris Removal	NO
В	Sediment Removal	> 100 FEET
С	Stormwater Basin Maintenance	NO
D	Drain Crossing Maintenance	NO
E	Enclosed Drain Maintenance	NO

DETAILED DRAWINGS AND SPECIFICATIONS ARE LOCATED IN THE MICHIGAN ASSOCIATION OF COUNTY DRAIN COMMISSIONERS SOIL EROSION AND SEDIMENTATION CONTROL AUTHORIZED PUBLIC AGENCY PROCEDURES MANUAL.

SYMBOLOGY FOR INSERTION INTO CONSTRUCTION DRAWINGS:



= PERMANENT MEASURE



 $\frac{\#}{\mathsf{T}}$ = TEMPORARY MEASURE

GENERAL TIMING & SEQUENCE

ALL PROPOSED CHANNEL EXCAVATION ACTIVTIES FOR THIS PROJECT MUST ADHERE TO THE FOLLOWING SEQUENCE.

- CONTRACTOR MUST CLEAR THE DRAIN CHANNEL AND RIGHT-OF-WAY AS NOTED PLANS. THIS INCLUDES ALL DEBRIS AND STUMP REMOVAL AS NOTED ON PLANS. CONTRACTOR MUST VERIFY WITH ENGINEER THAT CLEARING REQUIREMENTS HAVE BEEN MET PRIOR TO MOVING FORWARD WITH EXCAVATION.
- DRAIN EXCAVATION STAKES WILL BE PLACED FOLLOWING APPROVAL OF SITE CLEARING.
- 3. CONTRACTOR IS TO PERFORM PROPOSED EXCAVATION ACTIVITIES REQUIRED TO OBTAIN PROPOSED GRADES AND SIDE SLOPES AS DESIGNATED ON PLANS.
- 4. CONTRACTOR MUST PERFORM DAILY RAKING, SEEDING, AND MULCHING OF DRAIN BANKS AND SPOILS.
- 5. ENGINEER WILL STAKE ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES ALONG PORTIONS OF DRAIN THAT HAVE BEEN EXCAVATED DURING ROUTINE INSPECTIONS.
- 6. CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING SOIL EROSION AND SEDIMENT CONTROL MEASURES THROUGHOUT THE ENTIRE PROJECT.
- 7. FINAL PAYMENT WILL BE MADE ONCE ALL DRAIN BANKS, SPOILS, AND DISTURBED AREAS HAVE ESTABLISHED VEGETATION GROWING. ALL LAWN AREAS MUST BE RESTORED TO IN KIND CONDITIONS PRIOR TO FINAL PAYMENT.

SOIL CLASS	SOIL COMPOSITION
<i>5A</i>	Sumava sandy loam, 0 to 3 percent slopes
10C	Grattan sand, 4 to 12 percent slopes
12	Corunna sandy loam
13	Belleville fine sand
18	Lenawee silty clay loam, 0 to 1 percent slopes
22B	Parkhill-Selfridge complex, 0 to 2 percent slopes
24	Parkhill loam, 0 to 1 percent slopes
26A	Pipestone sand, loamy substratum, 0 to 3 percent slopes
29	Sloan silt loam, frequently flooded
31A	Pipestone sand, Erie-Huron Lake Plain, 0 to 3 percent slopes
33	Granby fine sand
44	Sloan-Ceresco complex, frequently flooded
58B	Covert sand, 1 to 6 percent slopes
60B	Arkona sand, 0 to 4 percent slopes
61A	Tappan-Poseyville complex, 0 to 3 percent slopes
70	Udipsamments, undulating
75B2	Strawn silt loam, 2 to 6 percent slopes, eroded
75C2	Strawn silt loam, 6 to 12 percent slopes, eroded
78	Fluvaquents, frequently flooded
82	Granby sand, loamy substratum
95	Sloan-Ceresco complex, rarely flooded
98A	98A—Poseyville loamy fine sand, 0 to 3 percent slopes
124A	Selfridge loamy sand, 0 to 3 percent slopes
CvrabA	Conover-Williamstown loams, 0 to 6 percent slopes
MtgaaA	Misteguay silty clay, 0 to 1 percent slopes, rarely flooded
ZwkaaA	Zilwaukee and Misteguay silty clays, 0 to 1 percent slopes, rarely flooded
ZwkabA	Zilwaukee and Misteguay silty clays, 0 to 1 percent slopes, frequently flooded

MAINTENANCE PROGRAM FOR SESC MEASURES

GENERAL MAINTENANCE

- CONTRACTOR SHALL MAINTAIN ALL PERMANENT SESC MEASURES FOR A PERIOD OF 1 YEAR FOLLOWING THEIR INSTALLATION.
- TEMPORARY SESC MEASURES MUST BE INSTALLED, MAINTAINED, AND REMOVED BY THE CONTRACTOR.
- TEMPORARY MEASURES MUST BE MAINTAINED AND IN PLACE UNTIL AREAS ARE PERMANENTLY STABILIZED.
- PERMANENT MEASURES MUST BE INSTALLED AND MAINTAINED BY THE CONTRACTOR UNTIL FINAL COMPLETION.
- DAILY MAINTENANCE IS THE CONTRACTOR'S RESPONSIBILITY.
- TEMPORARY SESC MEASURES MUST BE REMOVED AT THE END OF THE PROJECT ONCE PERMANENT MEASURES ARE ESTABLISHED.
- TEMPORARY SESC MEASURES MUST BE INSTALLED PRIOR TO OR AT THE TIME OF EARTH DISTURBANCE.
- INSPECT WEEKLY AND AFTER EACH RAIN EVENT UNTIL VEGETATION HAS BEEN ESTABLISHED.
- IF NECESSARY, REPAIR AND RE-SEED OR REPLANT ERODED AREAS IMMEDIATELY.

SEEDING AND MULCHING

- SEEDING PRACTICES INCLUDE TOPSOIL (AS DIRECTED BY ENGINEER), SEED, POLYMER, AND MULCH OR MULCH MATTING (AS DIRECTED BY ENGINEER OR WHERE SHOWN ON PLANS).
- WHERE NECESSARY, APPROPRIATE MULCH MUST BE APPLIED BASED ON SLOPE AND GROWING CONDITIONS AS APPROVED BY THE PROJECT MANAGER.
- ALL SLOPES AND HIGHLY EROSIVE ARES MUST BE SEEDED, POLYMER APPLIED, AND MULCHED AS NEEDED WHEN CONSTRUCTION ACTIVITY IS NOT TAKING PLACE.
- SEED AND MULCH IS TO BE INSPECTED DAILY FOLLOWING EACH RAIN EVENT TO DETERMINE IF CONCENTRATED FLOWS ARE PRESENT.
- IN THE EVENT THAT SEED AND MULCH ARE REMOVED BY EROSIVE RUNOFF, REPAIRS ARE TO BE MADE
- ALL AREAS DURING CONSTRUCTION MUST BE PERMANENTLY STABILIZED WITHIN 72 HOURS OF FINAL GRADE (GRADE LISTED ON PLAN).

STORM DRAIN INLET PROTECTION

- INSPECT ROUTINELY AND FOLLOWING A PRECIPITATION EVENT THAT RESULTS IN RUNOFF UNTIL SEDIMENT FILTER IS REMOVED.
- ROUTINELY REMOVE SEDIMENT ACCUMULATION.
- REPAIR AND REPLACE CONTROL MEASURES AS NEEDED.

STABILIZED CONSTRUCTION ACCESS

- INSPECT WEEKLY AND AFTER EACH RAINFALL.
- WHEN CONSTRUCTION ACCESS IS NO LONGER EFFECTIVE, SCRAPE THE TOP LAYER AND ADD 2" OF AGGREGATE.

COMPLIANCE WITH PART 91 OF PA 451

• RESPOND IMMEDIATELY TO STORMWATER OPERATOR AND/OR SOIL EROSION AND SEDIMENTATION CONTROL INSPECTOR'S CONCERNS. MAKE CORRECTIVE MEASURES AS REQUIRED IMMEDIATELY AS DETAILED BY THE APPROVED APA MANUAL(S).

SOIL EROSION AND SEDIMENTATION CONTROL NOTES

- 1. INSTALL AND MAINTAIN ALL TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED PLAN PRIOR TO COMMENCEMENT OF CONSTRUCTION OR MASS GRADING, ALL SESC MEASURES MUST BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE MARSH CREEK #2 DRAIN SESC PLAN AND PROJECT SPECIFICATIONS.
- 2. SOIL EROSION CONTROL MEASURES MUST BE INSPECTED BY A STATE CERTIFIED INSPECTOR AFFILIATED WITH THE COUNTY PUBLIC WORKS / COUNTY DRAIN COMMISSIONER'S OFFICE PRIOR TO COMMENCEMENT OF CONSTRUCTION OR MASS GRADING.
- 3. DAILY INSPECTION AND MAINTENANCE MUST BE MADE TO ENSURE ALL EROSION CONTROL MEASURES ARE FUNCTIONING PROPERLY AND INTACT. NECESSARY REPAIRS MUST BE PERFORMED WITHIN 24 HOURS.
- 4. ADDITIONAL SOIL EROSION CONTROL MEASURES MUST BE PROVIDED THROUGHOUT CONSTRUCTION ACTIVITY AS NEEDED AND DETERMINED BY THE APA/ENGINEER. THE SOIL EROSION AND SEDIMENTATION CONTROL PLAN IS TO BE AMENDED TO INCLUDE ADDITIONAL EROSION CONTROL MEASURES IMPLEMENTED
- 5. SEDIMENT FROM WORK ON THIS SITE IS TO BE CONTAINED ON THE SITE AND IS NOT TO BE ALLOWED TO COLLECT ON ANY OFF-SITE AREAS OR IN WATERWAYS. WATERWAYS INCLUDE BOTH NATURAL AND MANMADE OPEN DITCHES, STREAMS, STORM DRAINS, LAKES, PONDS, AND WETLANDS.
- 6. ALL VISUAL TRACKING INCLUDING MUD, DIRT, AND DEBRIS TRACKED ONTO EXISTING ROADWAYS MUST BE IMMEDIATELY REMOVED NO LESS THAN ON A DAILY BASIS BY SCRAPING AND SWEEPING AND/OR AS DIRECTED BY THE ENGINEER OR APA.
- 7. DUST CONTROL MUST BE EXERCISED AT ALL TIMES DURING THE PROJECT AND AS DIRECTED BY THE ENGINEER OR APA. APPLY DUST SUPPRESSANT TO SURFACES USING A PRESSURE TYPE WATER DISTRIBUTOR TRUCK EQUIPPED WITH A SPRAY SYSTEM.
- 8. ALL PERMANENT SOIL EROSION CONTROL MEASURES MUST BE IN PLACE WITHIN 24 HOURS OF FINAL GRADING (GRADE LISTED ON PLANS), THIS INCLUDES ALL VEGETATIVE STABILIZATION. VEGETATIVE STABILIZATION WILL BE ONGOING. TOPSOIL, FERTILIZER, SEED, POLYMER, SILT STOP (OR EQUAL), MULCH AND OR RIPRAP MUST BE IN PLACE BEFORE PROCEEDING TO THE NEXT WORK AREA. ALL TEMPORARY MEASURES SUCH AS SILT FENCE AND INLET PROTECTION BAGS ARE TO BE REMOVED ONCE PERMANENT SESC MEASURES ARE IN PLACE AND VEGETATION IS ESTABLISHED. REMOVAL OF TEMPORARY MEASURES, FOLLOWING ACCEPTANCE OF THE PROJECT IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 9. PRIOR TO WINTER CONSTRUCTION, ALL EXPOSED SOILS MUST BE STABILIZED WITH A COMBINATION OF SILT STOP 705 POLYMER BLEND, NORTH AMERICAN GREEN EROSION CONTROL BLANKETS. MULCH, OR OTHER APPROVED METHOD IF VEGETATION COULD NOT BE ESTABLISHED DURING THE GROWING SEASON AS DETERMINED BY THE APA OR ENGINEER.
- 10. WORK AREAS MUST BE STABILIZED WITH TOPSOIL, SEED, FERTILIZER, AND MULCH WITHIN 24 HOURS FOLLOWING CONSTRUCTION. VEGETATIVE STABILIZATION IS ONGOING THROUGHOUT THE PROJECT.
- 11. ALL SOIL EROSION CONTROL MEASURES MUST BE INSPECTED DAILY, THE STORM WATER OPERATOR IS TO MAKE A WEEKLY INSPECTION OR INSPECT AFTER EACH RAIN EVENT THAT RESULTED IN A DISCHARGE TO ENSURE PROPER MAINTENANCE OF THE SOIL EROSION CONTROL MEASURES. ANY DEFICIENCIES OR REPAIRS TO SOIL EROSION CONTROL MEASURES MUST BE CORRECTED IMMEDIATELY. INLET PROTECTION MEASURES, DANDY BAG II (OR EQUAL), FLEX STORM (OR EQUAL), MUST BE INSTALLED IN CATCHBASINS BEFORE ANY STORMWATER RUNOFF IS ALLOWED TO ENTER THE TOP OF THE STRUCTURES. THE SILT AND SEDIMENT MUST BE REMOVED FROM INLET PROTECTION MEASURES AS NEEDED TO ENSURE PROPER FUNCTION OF THE BAGS.
- 12. THE NEED FOR TEMPORARY MEASURES SUCH AS SILT FENCE AND DANDY BAG II (OR EQUAL), FLEX STORM (OR EQUAL) FOR EXISTING OR NEW CATCHBASINS MUST BE ASSESSED ON A DAILY BASIS. PIPES ARE TO BE CAPPED AT THE END OF EACH WORKDAY. AT NO TIME SHOULD SEDIMENT COLLECT IN A CATCHBASIN OR AN OFF-SITE AREA. TEMPORARY MEASURES MUST BE REMOVED ONCE PERMANENT MEASURES ARE IN PLACE AND VEGETATION IS ESTABLISHED.
- 13. IF DEWATERING IS NECESSARY, CONTRACTOR SHALL SUBMIT A DEWATERING PLAN TO THE ENGINEER OR APA FOR APPROVAL.
- 14. THE NOTICE OF COVERAGE (IF REQUIRED), SOIL EROSION AND SEDIMENTATION CONTROL PLAN, AND STORMWATER OPERATOR LOGS MUST BE LOCATED ON SITE AT ALL TIMES.
- 15. ALL RESTORATION TO OCCUR WITHIN 24 HOURS OF FINAL GRADING.

CONTINUED MAINTENANCE PROGRAM FOR PERMANENT SESC MEASURES							
RESPONSIBLE PARTY:	SAGINAW COUNTY PUBLIC WORKS COMMISSIONER						
PERMANENT SESC MEASURE	MAINTENANCE PROCEDURE						
SEEDING:	REPAIR BARE AREAS, APPLYING SUPPLEMENTAL SEED, MULCH, AND WATER AS NEEDED. MOWING CAN BE USED PERIODICALLY TO DISCOURAGE WEEDS.						
RIPRAP:	REPAIR AREAS WHERE ROCK HAS BEEN DISPLACED. EXPAND RIPRAP AREA IF NEEDED.						

BY MARK THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION,

> MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN

SOIL EROSION AND SEDIMENTATION CONTROL PLAN



DESIGN OR PURPOSE.

230 S. Washington Ave Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com


PROJECT NO. DE.BY: POC/CDV CH.BY: CDV 135292SG2023 DR. BY: MJC APP. BY: NDC SHEET **03** OF **23** FILE NO. DATE DECEMBER, 2024 DR-4707-03 SCALE NOT TO SCALE


SOIL EROSION & SEDIMENTATION CONTROL PLAN IN COMPLIANCE WITH SECTION 323.1703 OF

PART 91, SOIL EROSION AND SEDIMENTATION CONTROL, OF THE NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION ACT. 1994 PA 451, AS AMENDED.



MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN





1. STA 41+90 - CONTRACTOR TO CLEAR MAINTENANCE LANE ALONG BOTH SIDES OF PRYOR DRAIN TO WAHL ROAD IN ORDER TO ACCESS DOWNSTREAM OF STA 41+90.

© 2024	4
DE. BY: POC/C	DE. BY:

	,					VV VV VV	Spicei Gio	ир.сотт
		POC/CDV MJC	-			1.		ECT NO. ?SG20
-	STDS.			SHEET	05	OF	23	D
		DECEMBE H: 1"=200' V		FILE NO	R-47	07-0	95	0

230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440

RIGHT OF WAY MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 75' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.



	<i>×</i>							
595	NO. 3 DK							<i>595</i>
590	\times_\t							590
585	I I		- TOP OF RANK LEFT	OF BANK RIGHT				
580			CPP / 580.48		18" ??		12" PVC INV 581.10	580
575								575
570	CLEAR MAINTENANCE LANE							570
565	AND REMOVE LOG JAMS - WORK FROM LEFT SIDE							565
560					TENANCE LANES VE LOG JAMS -			560
				WORK FRO	M BOTH SIDES			
50+00	54+53	65+00	70+00	75+00	80+00	85+00	00+00	100+00

	EROSION CONTROL TABLE									
KEY*	FROM STATION	TO STATION	SIDE	DESCRIPTION	QTY					
$\frac{1}{P}$	50+00	100+00	ВОТН	SEEDING OF ALL DISTURBED	LUMP SUM					
$\frac{2}{1}$	50+00	100+00	ВОТН	MULCH OF ALL DISTURBED AREAS	LUMP SUM					
(23) P	' ' '	IELD TILE AND S.O.T.	ВОТН	OUTFALL STABILIZATION	4 EA					

NOTE: COORDINATE INSTALLATION OF EROSION CONTROL STRUCTURES WITH ENGINEER PRIOR TO CONSTRUCTION. LOCATIONS, QUANTITIES, OR TYPES MAY VARY BASED ON FIELD DECISIONS.

CONSTRUCTION NOTES

- 1. STA 58+00 CONSTRUCT TURNAROUND ON RIGHT SIDE PER DETAIL SHOWN ON SHEET 22.
- 2. STA 92+00 TO STA 100+00, RIGHT SIDE CONTRACTOR TO WIND ROW ALL TREES AND BRUSH OUTSIDE DRAIN RIGHT-OF-WAY.

RIGHT OF WAY

MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 75' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.

BY	MARK	REVISIONS	DATE
SPECIFIC WITH THE DOES NO	APPLICATION E CONDITION	INTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR T DN AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE IN SPREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINE BE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION	ER

MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN

PLAN AND PROFILE STA 50+00 TO STA 100+00




SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

p.com	www.SpicerGrou			© 2024			
CT NO. SG2023	PROJE 135292			CH. BY: APP. BY	POC/CDV MJC	E. BY: R. BY:	
DR	of 23	06	SHEET			TDS.	

DATE DECEMBER, 2024 SCALE H: 1"=200' V: 1"=10' DR-4707-06 06 06 23 DM

NProj2023\135292SG2023 • Marsh Creek #2 Drain\2_AutoCAD_GIS\dwg\DR-4707-05-06




MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 75' WIDE ON EACH SIDE OF

CENTERLINE OF DRAIN.

DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' **DR-**

DR-4707-07

/2023\135292SG2023 - Marsh Creek #2 Drai



NO. 05 - STA 182+02 - SPENCER ROAD CLEANOUT EXISTING CROSSING

EROSION CONTROL TABLE								
KEY*	FROM STATION	TO STATION	SIDE	DESCRIPTION	QTY			
	150+00	200+00	вотн	SEEDING OF ALL DISTURBED	LUMP SUM			
$\frac{2}{1}$	150+00	200+00	ВОТН	MULCH OF ALL DISTURBED AREAS	LUMP SUM			
(16) P		KED BY NEER	-	RIPRAP TOE OF SLOPE PROTECTION	400 LIN FT			
19 P	AS STAKED BY ENGINEER		-	RIPRAP SPILLWAY	130 LIN FT			
(23) P		TELD TILE AND S.O.T.	ВОТН	OUTFALL STABILIZATION	3 EA			
NOTE:	COORDINA	ATE INISTAL	LATION	OF FROSION CONTRO				

NOTE: COORDINATE INSTALLATION OF EROSION CONTROL STRUCTURES WITH ENGINEER PRIOR TO CONSTRUCTION. LOCATIONS, QUANTITIES, OR TYPES MAY VARY BASED ON FIELD DECISIONS.

SPOIL LEVELING TABLE					
STATION FROM	STATION TO	DETAIL	SIDE TO EXCAVATE FROM		
150+00	188+00	В	ВОТН		
188+00	198+00	HAUL	LEFT		
		В	RIGHT		

BOTH

198+00

USE SPOIL LEVELING DETAIL "A" THROUGH FIELD AREA. USE SPOIL LEVELING DETAIL "B" THROUGH WOODED AREA. SPOILS TO BE HAULED IN LAWN AREAS.

STA 182+12 SEE CONSTRUCTION NOTE 2 THIS SHEET

200+00

MAINTENANCE ACCESS					
STATION	SIDE	SIZE/TYPE	LENGTH		
181+82	LEFT	15" CULVERT	40 LIN FT		
182+12	LEFT	36" RCP	24 LIN FT		
COORDINATE INSTALLATION OF ACCESS CULVERTS WITH ENGINEER PRIOR TO CONSTRUCTION					

CONSTRUCTION NOTES

- 1. STA 160+00 AND STA 161+00 LEFT SIDE: CONSTRUCT TURNAROUND AS NEEDED PER DETAIL ON SHEET 22.
- 2. STA 182+16 LEFT SIDE: INSTALL 24 LIN FT OF 36" RCP EXTENSION ON UPSTREAM END OF EXISTING ACCESS CULVERT. INSTALL CONCRETE COLLAR AT CONNECTION TO EXISTING CULVERT.
- 3. STA 182+16 RIGHT SIDE: INSTALL ACCESS RAMP OFF OF SPENCER ROAD PER DETAIL ON SHEET 23. FILL MATERIAL MUST BE APPROVED BY ENGINEER PRIOR TO INSTALLATION.

BENCHMARKS

BM 206 - SET GEAR SPIKE IN NORTHWEST FACE OF POWER POLE BEING ±40' SOUTEAST OF SPENCER ROAD AND ±50' EAST OF CL OF MARSH CREEK BEING ±80' WEST OF CL OF HOUSE DRIVEWAY #11890.

EL 591.54

RIGHT OF WAY

MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 75' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.

BY	MARK	REVISIONS	DAT		
THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.					

MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN


PLAN AND PROFILE STA 150+00 TO STA 200+00



230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com


DE. BY: POC/CDV CH. BY: CDV DR. BY: MJC APP. BY: NDC PROJECT NO. *135292SG2023*


DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' **DR-***DR-4707-08*



DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' **DR-***DR-4707-09*







NO. 09 - STA 276+64 - ORR ROAD CLEANOUT EXISTING CROSSING

NO. 10 - STA 285+89 - ROOSEVELT ROAD CLEANOUT EXISTING CROSSING

NO. 11 - STA 292+92 - ZELINKO FARMS REALTY LLC REMOVE EXISTING CROSSING

	EROSION CONTROL TABLE						
KEY*	FROM STATION	TO STATION	SIDE	DESCRIPTION	QTY		
$\frac{1}{P}$	250+00	300+00	ВОТН	SEEDING OF ALL DISTURBED	LUMP SUM		
$\frac{2}{1}$	250+00	300+00	ВОТН	MULCH OF ALL DISTURBED AREAS	LUMP SUM		
16 P	AS STAKED BY ENGINEER		-	RIPRAP TOE OF SLOPE PROTECTION	600 LIN FT		
19 P	AS STAKED BY ENGINEER		1	RIPRAP SPILLWAY	50 LIN FT		
23 P	ALL EX FIELD TILE OUTLETS AND S.O.T.		ВОТН	OUTFALL STABILIZATION	4 EA		

NOTE: COORDINATE INSTALLATION OF EROSION CONTROL STRUCTURES WITH ENGINEER PRIOR TO CONSTRUCTION. LOCATIONS, QUANTITIES, OR TYPES MAY VARY BASED ON FIELD DECISIONS.

SPOIL LEVELING TABLE					
STATION FROM	STATION TO	DETAIL	SIDE TO EXCAVATE FROM		
250+00	261+00	В	ВОТН		
261+00	281+98	А	ВОТН		
281+98	285+39	А	LEFT		
		HAUL	RIGHT		
285+39	300+00	В	ВОТН		

USE SPOIL LEVELING DETAIL "A" THROUGH FIELD AREA. USE SPOIL LEVELING DETAIL "B" THROUGH WOODED AREA. SPOILS TO BE HAULED IN LAWN AREAS.

MAINTENANCE ACCESS					
STATION	SIDE	SIZE/TYPE	LENGTH		
277+04	RIGHT	15" CULVERT	40 LIN FT		
287+14	RIGHT	30" CULVERT	40 LIN FT		
COORDINATE INSTALLATION OF ACCESS CULVERTS WITH ENGINEER PRIOR TO CONSTRUCTION.					

BENCHMARKS

BM 204 - SET GEAR SPIKE IN SOUTHEAST FACE OF POWER POLE BEING ±40' NORTH OF CL OF ROOSEVELT ROAD BEING ±30' WEST OF CL OF MARSH CREEK.

EL 600.65

BM 205 - SET ON EAST FLANGE BOLT OF RED HYDRANT BEING ±40' SOUTH OF CL OF MARSH CREEK AND ±25' EAST OF CL OF ORR ROAD BEING ±30' NORTHEAST OF THE SOUTH END OF GUARD RAIL.

EL 605.56

RIGHT OF WAY

MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY FROM STA 250+00 TO STA 276+64 IS 75' WIDE ON EACH SIDE OF CENTERLINE OF

DRAIN RIGHT-OF-WAY FROM STA 276+64 TO STA 300+00 IS 66' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.

BY	MARK	REVISIONS	DAT			
	THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE					
WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER						
DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION,						
DESIGN OR PURPOSE.						

MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN


PLAN AND PROFILE STA 250+00 TO STA 300+00



SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440

© 2024 Group				SpicerGrou	
BY: POC/CDV CH. BY: BY: MJC APP. BY:	CDV NDC		13		CT NO. SG20 2
S.	SHEET 10	0	OF	23	Di


DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' DR-




PRIOR TO CONSTRUCTION.

MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 66' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.

SHEET 11 OF 23 DR DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' **DR-**DR-4707-11



3\135292SG2023 - Marsh Creek #2 Drain\2_A



NO. 17 - STA 427+82 - GLOVER, D & K CLEANOUT EXISTING CROSSING

NO. 18 - STA 443+46 - BEYERSDORF, L & M CLEANOUT EXISTING CROSSING

EROSION CONTROL TABLE						
KEY*	FROM STATION	TO STATION	SIDE	DESCRIPTION	QTY	
	400+00	450+00	ВОТН	SEEDING OF ALL DISTURBED	LUMP SUM	
(<u></u>	400+00	450+00	ВОТН	MULCH OF ALL DISTURBED AREAS	LUMP SUM	
16 P	AS STAKED BY ENGINEER		-	RIPRAP TOE OF SLOPE PROTECTION	100 LIN FT	
19 P	AS STAKED BY ENGINEER		1	RIPRAP SPILLWAY	20 LIN FT	
23 P	ALL EX FIELD TILE OUTLETS AND S.O.T.		ВОТН	OUTFALL STABILIZATION	7 EA	
15 P	CROSSINGS 17-18		ВОТН	INSTALL RIPRAP PROTECTION AT INLET & OUTLET OF CROSSING	30 SQ YDS TOTAL	
IOTE.	COORDINI	ATE INISTAL	LATION	OF FROSION CONTRO	0/	

NOTE: COORDINATE INSTALLATION OF EROSION CONTROL STRUCTURES WITH ENGINEER PRIOR TO CONSTRUCTION. LOCATIONS, QUANTITIES, OR TYPES MAY VARY BASED ON FIELD DECISIONS.

	SPOIL LEVELING TABLE					
STATION FROM	STATION TO	DETAIL	SIDE TO EXCAVATE FROM			
400+00	407+00	А	ВОТН			
407+00	411+00	В	ВОТН			
411+00	413+00	А	LEFT			
		В	RIGHT			
413+00	427+82	В	ВОТН			
427+82	450+00	А	RIGHT			

USE SPOIL LEVELING DETAIL "A" THROUGH FIELD AREA. USE SPOIL LEVELING DETAIL "B" THROUGH WOODED AREA. SPOILS TO BE HAULED IN LAWN AREAS.

MAINTENANCE ACCESS				
STATION	SIDE	SIZE/TYPE	LENGTH	
412+20	LEFT	24" CULVERT	40 LIN FT	
COORDINATE INSTALLATION OF ACCESS CULVERTS WITH ENGINEER PRIOR TO CONSTRUCTION.				

STA 400+00 TO STA 450+00

DE. BY: POC/CDV CH. BY: CDV

SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

DR. BY: MJC APP. BY	: NDC	135292	SG2023
STDS.	SHEET 13	of 23	DR
DATE DECEMBER, 2024 SCALE H: 1"=200' V: 1"=10'	FILE NO. DR-47 (07-13	13


REVISIONS


MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN


PLAN AND PROFILE

THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.

RIGHT OF WAY MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 66' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.







NO. 19 - STA 466+67 - BORN, D CLEANOUT EXISTING CROSSING

NO. 20 - STA 479+41 - JUNGNITSCH, F & D CLEANOUT EXISTING CROSSING

NO. 21 - STA 482+40 - JUNGNITSCH, F & D REMOVE EXISTING CROSSING, INSTALL 50 LIN FT OF 48" HP STORM RESTORE NATIVE DRIVE

NO. 22 - STA 498+96 - EDERER ROAD REMOVE EXISTING CROSSING, INSTALL 60 LIN FT OF 42" HP STORM RESTORE BITUMINOUS ROAD

EROSION CONTROL TABLE								
FROM STATION	TO STATION	SIDE	DESCRIPTION	QTY				
450+00	499+70	ВОТН	SEEDING OF ALL DISTURBED	LUMP SUM				
450+00	<i>499+70</i>	ВОТН	MULCH OF ALL DISTURBED AREAS	LUMP SUM				
AS STAKED BY ENGINEER		-	RIPRAP TOE OF SLOPE PROTECTION	200 LIN FT				
		ВОТН	OUTFALL STABILIZATION	6 EA				
CROSSINGS 21 & 22		ВОТН	INSTALL RIPRAP PROTECTION AT INLET & OUTLET OF CROSSING	60 SQ YDS TOTAL				
	STATION 450+00 450+00 AS STA ENGL	FROM TO STATION 450+00 499+70 450+00 499+70 AS STAKED BY ENGINEER ALL EX FIELD TILE OUTLETS AND S.O.T.	FROM TO SIDE 450+00 499+70 BOTH 450+00 499+70 BOTH AS STAKED BY ENGINEER - ALL EX FIELD TILE OUTLETS AND S.O.T. BOTH	FROM STATIONTO STATIONSIDEDESCRIPTION450+00499+70BOTHSEEDING OF ALL DISTURBED450+00499+70BOTHMULCH OF ALL DISTURBED AREASAS STAKED BY ENGINEER-RIPRAP TOE OF SLOPE PROTECTIONALL EX FIELD TILE OUTLETS AND S.O.T.BOTHOUTFALL STABILIZATIONCROSSINGS 21 & 22BOTHINSTALL RIPRAP PROTECTION AT INLET & OUTLET				

NOTE: COORDINATE INSTALLATION OF EROSION CONTROL STRUCTURES WITH ENGINEER PRIOR TO CONSTRUCTION. LOCATIONS, QUANTITIES, OR TYPES MAY VARY BASED ON FIELD DECISIONS.

	SPOIL LEVELING TABLE					
STATION FROM	STATION TO	DETAIL	SIDE TO EXCAVATE FROM			
450+00	498+72	А	RIGHT			

USE SPOIL LEVELING DETAIL "A" THROUGH FIELD AREA. USE SPOIL LEVELING DETAIL "B" THROUGH WOODED AREA. SPOILS TO BE HAULED IN LAWN AREAS.

CONSTRUCTION NOTES

- 1. VERIFY DEPTHS AND LOCATIONS OF ALL UTILITIES ALONG ROAD PRIOR TO REMOVING EXISTING CROSSING IF CROSSING IS REPLACED. ALL COST ARE TO BE INCLUDED IN ALTERNATE BID ITEM FOR CULVERT REPLACEMENT.
- 2. STA 498+68 DIRECT 15" CMP TILE TO DOWNSTREAM END OF PROPOSED CROSSING USING 45° BEND AS NEEDED. TO BE PAID AS FIELD TILE

BENCHMARKS

BM 200 - SET GEAR SPIKE IN N FACE OF POWER POLE BEING ±30' SOUTH OF CL OF EDERER ROAD AND SOUTHWEST QUADRANT OF EDERER ROAD AND WATSON DRIVE BEING ±125' E OF CL OF MARSH CREEK.

EL 635.65

RIGHT OF WAY

MARSH CREEK #2 DRAIN - DRAIN RIGHT-OF-WAY IS 66' WIDE ON EACH SIDE OF CENTERLINE OF DRAIN.

BY	MARK	REVISIONS	DATE
PECIFIC ITH THE DES NO	APPLICATION CONDITION	NTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR TO IN AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE IS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINE IS EE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITIONS.	ER

MARSH CREEK #2 DRAIN SAGINAW COUNTY, MICHIGAN


PLAN AND PROFILE STA 450+00 TO STA 499+70




230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

DE. BY: POC/CDV CH. BY: CDV DR. BY: MJC APP. BY: NDC PROJECT NO. *135292SG2023* SHEET 14 OF 23 DR DATE DECEMBER, 2024 FILE NO. SCALE H: 1"=200' V: 1"=10' **DR-**


DR-4707-14




P:\Proj2023\135292SG2023 - Marsh Creek #2 Drain\2_AutoCAD_GIS\dwg\DR-4707-15-




P.\Proj2023\135292SG2023 - Marsh Creek #2 Drain\2_Aui







P.\Pro|2023\135292SG2023 - Marsh Creek #2 Drain\2_AutoCAD_GIS\dwg\DR




DR-4707-19



P:\Proj2023\135292SG2023 - Marsh Creek #2 Drain\2_AutoCAI





.Proj2023\135292SG2023 - Marsh Creek #2 Drain\2_AutoCAD_GIS

.

