BABCOCK DRAIN

BRIAN J. WENDLING, SAGINAW CO. PUBLIC WORKS COMMISSIONER

SECTION 9, T9N, R4E MAPLE GROVE TWP. SAGINAW CO. MICHIGAN

GENERAL

1. Benchmarks

- #1. Found Remon/Monument Box Saginaw County Monument, stamped 39096, in existing Monument Box. 1/4 corner, Sections 4, 9, T9N-R4E, Maple Grove Township, Saginaw County, Michigan. Elevation = 635.83 (Datum = NAVD88)
- #2. Found Remon/Monument Box Saginaw County Monument, stamped 39096, in existing Monument Box. Section Corner, Sections 4, 5, 8, 9, T9N-R4E, Maple Grove Township, Saginaw County, Michigan. Elevation = 635.89 (Datum = NAVD88)
- 2. The contractor shall call "MISS DIG" at 811 or 1-800-482-7171 at least 3 working days (excluding weekends and holidays) prior to construction.
- 3. All work shall be done in accordance with the applicable codes, ordinances, design standards and standard specifications of the following agencies which have the responsibility of reviewing plans and specifications for construction of all items included in these plans:
 - a. Saginaw County Public Works Commissioner b. Saginaw County Road Commission c. Michigan Department of Environment, Great Lakes,
- 4. The contractor shall apply for and obtain all necessary permits as required for construction of this project prior to the beginning of work from the previously mentioned
- 5. The contractor shall notify the Saginaw County Road Commission a minimum of 24 hours prior to any construction in the road right-of-way of Chesaning Road.
- 6. The contractor garees that in accordance with generally accepted construction practices, the contractor will be required to assume sole responsibility for job site conditions during the course of construction of the project, including the safety of all persons and property. This requirement shall be made to apply continuously and not be limited to normal working hours.
- 7. The locations and dimensions shown on the plans for existing facilities are in accordance with all available information. The engineer does not guarantee the accuracy of this information or that all existing underground facilities are shown.
- 8. When any existing utility requires adjustment or relocation, the contractor shall notify the proper utility company and coordinate the work accordingly. There shall be no claim made by the contractor for any costs caused by delays in construction due to the adjustment or relocation of
- 9. The contractor is to verify that the plans and specifications that he/she is building from are the very latest plans and specifications that have been approved by all applicable permit—issuing agencies and the owner. All items constructed by the contractor prior to receiving the final approval and permits having to be adjusted or re-done, shall be done at the contractor's expense.
- 10. Should the contractor encounter conflict between these plans and specifications, either among themselves or with the requirements of any and all reviewing and permit—issuing agencies, he/she shall seek clarification in writing from this engineer before commencement of to the contractor.
- as—built drawings indicating all changes and deviations from approved drawings.
- 12. All signs and traffic control measures during construction and maintenance activities shall be constructed and Uniform Traffic Control Devices (M.M.U.T.C.D.)
- 13. LSG Engineers & Surveyors will not be responsible for field design changes made by the contractor or the contractor's surveyor where LSG Engineers & Surveyors has not approved these design changes.

GRADING AND SITE WORK

- 1. All sedimentation and soil erosion control measures shall be constructed prior to the commencement of site grading and must conform to Part 91 of Act 451 of the Public Acts of 1994 as amended. All applicable permits shall be obtained before implementing these measures. The contractor shall be responsible for maintaining the sedimentation and soil erosion control measures throughout construction.
- 2. Prior to grading, cutting and filling the contractor shall remove all topsoil, debris, vegetation, etc. from the site.
- 3. All site grading must be performed to insure positive drainage across the entire site, throughout the period of construction and after project completion.

STORM DRAINAGE SYSTEM

- 1. Unless otherwise noted all storm drain pipe shall be AASHTO M36 corrugated steel.
- 2. All storm drain within the influence of roads, drives, walks, structures and foundations shall be backfilled with 100% granular material (or approved other) and compacted to 95% of its maximum unit weight (see typical trench details included in these plans).
- 3. See drain details on sheets C2.0.

CONSTRUCTION NOTES

- 1. No piling of debris will be allowed on this project, debris shall be chipped, or hauled away.
- 2. Field diversion swales are incidental to the construction for spoil leveling (see details this sheet). Field diversions required for Soil Erosion Control Measures will be measured by linear foot.
- 3. Sediment sumps will be constructed on this project. All sumps are to be maintained regularly throughout construction and cleaned out upon completion of this
- 4. Upon completion of the project, all rock check dams shall be removed incidental to construction. All sediment that has been accumulated behind the check dams shall be removed from the drain and leveled according to the spoil
- 5. Fences on private property disturbed by the contractor on this project will be replaced as per general conditions.
- 6. The contractor will be responsible for turf establishment along drain side slopes, spoil banks, culvert end slopes and other areas designated by the construction plans or by the engineer as per the open drain specifications.
- 7. Drain inspection cost will be paid by the owner. Inspection charges by the road commission, railroads and the M.D.O.T. will be paid by the contractor, unless otherwise

(E) CULVERT

(E) SIGN

(E) MAILBOX


(P) RIP RAP LOW POINT


HIGH POINT

FINISH FLOOR

BENCHMARK

(P) BASIN AREA IN ACRES





2.52

INDEX

C1.0	PLAN	AND	PROFII F	_	P.O.B.	TO STA	11+

PLAN AND PROFILE - STA 11+50 TO P.O.E.

REVISIONS/SUBMITTALS

CROSS SECTIONS

DRAIN NOTES AND DETAILS

DRAIN DETAILS DRAIN DETAILS

SOIL EROSION CONTROL PLAN

SOIL EROSION CONTROL DETAILS

TRAFFIC DETOUR PLAN

LSG ENGINEERS AND SURVEYORS

ALAN BOYER, P.E. 3135 PINE TREE ROAD. SUITE D LANSING, MI 48911 PHONE: (517) 393-2902

SAGINAW COUNTY ROAD COMMISSION

HALEY SHEPHERD 3020 SHERIDAN AVE. SAGINAW, MI 48601 PHONE: (989) 752-6140

CONSUMERS ENERGY COMPANY - GAS


JOSEPH RODEA 530 W WILLOW ST. LANSING, MI 48906 PHONE: (989) 791-5869

EMAIL: JOSEPH.RODEA1@CMSENERGY.COM

CENTURY LINK BOBBY WALTER

203 W 9TH ST. LORAIN, OH 44052 PHONE: (440) 244-8415

EMAIL: BOBBY.D. WALTERS@CENTURYLINK.COM



SAGINAW COUNTY PUBLIC WORKS COMMISSIONER BRIAN J. WENDLING

111 S. MICHIGAN AVENUE SAGINAW, MICHIGAN PHONE: (989) 790-5258




SUITE D LANSING, MI 48911 PH. (517) 393-2902 FAX (517) 393-2608 www.lsg-es.com


MARCH 18, 2022 2409 SHEET NO.

EGLE PERMIT NO. WRP 026900 v.1

construction. Failure to do so shall be at the sole expense 11. Unless otherwise noted the contractor shall furnish

installed per the latest edition of the Michigan Manual of





11+50

12+00

13+00

14+00

15+00

16+00

17+00

18+00

19+00

20+00

21+00

22+00

23+00

24+00

Scale 1" = 50'

EXISTING EDGE OF WOOD

APPROXIMATES EXISTING WETLAND BOUNDARY

CENTER SECTION 9-


- EXISTING 6" WOOD POST 5' TALL

EGLE PERMIT NO.

MISS

WRP 026900 v.1

STA. 23+86
TO STA. 24+36
PLACE COMPACTED




Engineers & Surveyors

3135 PINE TREE ROAD SUITE D LANSING, MI 48911 PH. (517) 393-2902 FAX (517) 393-2608 www.lsg-es.com

DRAWN BY ____SEP/AJI CHECKED BY ADB DATE _____JAN. 11, 2021

PROJECT NO.

2409 C1.1



Engineers & Surveyors

3135 PINE TREE ROAD SUITE D LANSING, MI 48911 PH. (517) 393-2902 FAX (517) 393-2608 www.lsg-es.com

CROSS SECTIONS
FOR
BABCOCK DRAIN
MAPLE GROVE TOWNSHIP
SAGINAW COUNTY, MICHIGAL

Know what's below.


Call before you dig. EGLE PERMIT NO. WRP 026900 v.1

DESIGNED BY ADB

DRAWN BY SEP/AJI

CHECKED BY ADB DATE _____JAN. 11, 2021 HOR. 1" = 10'vert. <u>1" = 5'</u> PROJECT NO. 2409

SHEET NO. C2.0



1. REFER TO THE CONSTRUCTION SPECIFICATIONS FOR THE DEFINITION OF

2. NO PILING OF DEBRIS WILL BE ALLOWED ON THIS PROJECT. DEBRIS SHALL

3. IN CLEAR AND SNAG AREAS ONLY, THE CONTRACTOR WILL BE REQUIRED TO CLEAR, SNAG AND REMOVE DEBRIS DAMS WITHIN TOP WIDTH OF DRAIN, CLEAR BOTH BANKS IN ORDER TO PERFORM REQUIRED WORK WITHIN A MIN. OF 12', IF ANY OLD SPOIL IS PRESENT, CLEAR AS NECESSARY TO ALLOW FOR LEVELING OF SPOIL TO A MINIMUM OF 16' TOP WIDTH, AND REMOVE AND DISPOSE OF ALL DEBRIS. NO GRUBBING WILL BE ALLOWED WITHIN TOP WIDTH OF DRAIN. IF SLOPES ARE DISTURBED WHEN TREES ARE CUT AND REMOVED FROM SLOPES, THE CONTRACTOR WILL PREPARE SEED

SPECIFICATIONS AND DETAILS SHOWN ON THIS SHEET. SPOIL LEVELING IN

5. FOR SPOIL DEPOSITING ON ONE SIDE ONLY (TYPE C AND G) THE 12 FOOT STRIP CALLED FOR IN THE OPEN DRAIN SPECIFICATIONS WILL BE REQUIRED

6. FIELD DIVERSION SWALES ARE INCIDENTAL TO THE CONSTRUCTION FOR SPOIL LEVELING (SEE DETAILS THIS SHEET). FIELD DIVERSIONS REQUIRED FOR SOIL EROSION CONTROL MEASURES WILL BE MEASURED BY LINEAR

OPEN DRAIN SPECIFICATIONS. ALL SUMPS ARE TO BE MAINTAINED REGULARLY THROUGHOUT CONSTRUCTION AND CLEANED OUT UPON

REMOVED INCIDENTAL TO CONSTRUCTION. ALL SEDIMENT THAT HAS BEEN ACCUMULATED BEHIND THE CHECK DAMS SHALL BE REMOVED FROM THE DRAIN AND LEVELED ACCORDING TO THE SPOIL LEVELING DETAILS.

11. THE CENTERLINE OF THE DRAIN WILL BE SET BACK FROM ROADS AS

12. FENCES ON PRIVATE PROPERTY DISTURBED BY THE CONTRACTOR ON THIS

13. THE CONTRACTOR WILL BE RESPONSIBLE FOR TURF ESTABLISHMENT ALONG DRAIN SIDE SLOPES, SPOIL BANKS, CULVERT END SLOPES AND OTHER AREAS DESIGNATED BY THE CONSTRUCTION PLANS OR BY THE ENGINEER

CHARGES BY THE ROAD COMMISSION, RAILROADS AND THE M.D.O.T. WILL

LINE OPENING WITH RIPRAP (MDOT PLAIN) WHERE EROSIVE SOILS ARE PRESENT

SPOIL OPENING FOR FIELD DIVERSIONS (A)



Know what's below. Call before you dig. EGLE PERMIT NO. WRP 026900 v.1

DRAWN BY ____AJI_ CHECKED BY ADB DATE _____JAN. 11, 2021 HOR. <u>N/A</u> /ERT. <u>N/A</u> PROJECT NO.

DRAIN NOTES

Engineers

& Surveyors

3135 PINE TREE ROAD

SUITE D

LANSING, MI 48911


PH. (517) 393-2902


FAX (517) 393-2608

www.lsg-es.com

2409

C3.0





STANDARD EROSION AND

SEDIMENTATION CONTROL PLAN NOTES

1. SITE BENCHMARK #1 -

FOUND REMAN/MONUMENT BOX SAGINAW COUNTY MONUMENT, STAMPED 39096, IN EXISTING MONUMENT BOX. 1/4 CORNER, SECTIONS 4, 9, T9N-R4E, MAPLE GROVE TOWNSHIP, SAGINAW COUNTY, ELEVATION = 635.83 (DATUM = NAVD88)

2. SITE BENCHMARK #2 -

FOUND REMAN/MONUMENT BOX SAGINAW COUNTY MONUMENT. STAMPED 39096. IN EXISTING MONUMENT BOX. SECTION CORNER. SECTIONS 4, 5, 8, 9, T9N-R4E, MAPLE GROVE TOWNSHIP, SAGINAW COUNTY, MICHIGAN. ELEVATION = 635.89 (DATUM = NAVD88)

- 3. CONTRACTOR IS TO CONTACT SAGINAW COUNTY DRAIN COMMISSIONER AND THE MAPLE GROVE TOWNSHIP OF SAGINAW COUNTY, MICHIGAN, AT LEAST THREE (3) DAYS PRIOR TO THE START OF CONSTRUCTION.
- 4. THE SITE IS MADE UP OF PARKHILL LOAM & SELFRIDGE LOAMY SAND WHICH ARE CONSIDERED ERODIBLE SOILS.
- 5. FOR LAND AREAS POSSESSING SLOPES EXCEEDING 15% THE CONTRACTOR
 - A. PROTECT AND STABILIZE AREAS THAT HAVE A HIGH POTENTIAL FOR SOIL EROSION.
 - B. ASSURE STRUCTURAL SAFETY AND MINIMIZE HARM TO THE ENVIRONMENT ASSOCIATED WITH THE DEVELOPMENT.
 - C. MINIMIZE GRADING THROUGHOUT THE SITE.
 - D. PROTECT AND PRESERVE ANY VALUABLE NATURAL WILDLIFE AND/OR PLANT HABITATS WHICH COINCIDES WITH THE STEÉP-SLOPE AREAS OF THE SITE.
 - E. PROTECT WATER QUALITY ON AND AROUND THE SITE FROM THE ADVERSE EFFECTS OF THE PROPOSED USE.
 - F. PROTECT ANY STEEP SLOPES ON ADJOINING PROPERTIES.
- 6. ALL SLOPES GREATER THAN 6:1 SHALL BE SEEDED AND STABILIZED

IMMEDIATELY AFTER GRADE IS ESTABLISHED.

- 7. CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING ALL SOIL EROSION CONTROL MEASURES ON A WEEKLY BASIS. DURING CONSTRUCTION OWNER SHALL MAINTAIN ALL PERMANENT S.E.C. MEASURES AFTER CONSTRUCTION IS COMPLETE
- 8. ALL TEMPORARY S.E.C. MEASURES SHALL BE MAINTAINED 30 DAYS AFTER CONSTRUCTION IS COMPLETE OR UNTIL GRADED AREAS ARE STABILIZED. AT THIS TIME OWNER IS RESPONSIBLE FOR REMOVAL AND PROPER DISPOSAL OF THESE S.E.C. MEASURES.

- 9. ALL GRADED AREAS EXPOSED FOR MORE THAN 20 DAYS SHALL HAVE STRAW MULCH APPLIED AT THE RATE OF 3 TONS / ACRE. AREAS NOT AT FINISHED GRADE AND WHICH WILL BE DISTURBED AGAIN WITHIN ONE YEAR MUST BE SEEDED AND MULCHED WITH QUICK GROWING TEMPORARY SEEDING MIXTURE AND MULCH. AREAS WHICH ARE AT FINISHED GRADE AND WILL NOT BE DISTURBED FOR A YEAR MUST BE SEEDED AND MULCHED WITH A PERMANENT SEED MIXTURE.
- 10. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS TO THE SITE FOR GRADING AND TO CONSTRUCT SEDIMENT BASINS, SEDIMENT TRAPS, DIVERSION TERRACES, INTERCEPTOR CHANNELS, AND/OR CHANNELS OF CONVEYANCE AS APPROPRIATE.
- 11. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITH THE TRIBUTARY AREAS OF THOSE CONTROLS.
- 12. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE STABILIZED
- 13. SILT FABRIC FENCE MUST BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION MUST EXTEND AT LEAST 10 FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
- 14. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE SILT FENCE.
- 15. ANY SILT FENCE SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET.
- 16. STORM WATER INLETS WHICH DO NOT DISCHARGE TO SEDIMENT TRAPS OR BASINS, MUST BE PROTECTED UNTIL THE TRIBUTARY AREAS ARE
- 17. SEDIMENT MUST BE REMOVED FROM INLET PROTECTION AFTER EACH STORM
- 18. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE 2:1 OR FLATTER.
- 19. ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 20 DAYS MUST BE STABILIZED
- 20. DIVERSIONS, CHANNELS, SEDIMENTATION BASINS, SEDIMENT TRAPS, AND STOCKPILES MUST BE STABILIZED IMMEDIATELY.
- 21. HAY OR STRAW MULCH MUST BE APPLIED AT RATES OF AT LEAST 3
- 22. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROL AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY.

FOUND REMON/MONUMENT BOX

SAGINAW COUNTY MONUMENT,

STAMPED 39096.

NORTH 1/4 CORNER

SECTION 9, T9N, R4E

BELLEVILLE FINE SAND

PARKHILL LOAM (0 TO 1 PERCENT SLOPES)

124A SELFRIDGE LOAMY SAND (0 TO 3 PERCENT SLOPES)

COVERT SAND (1 TO 6 PERCENT SLOPES)

SESC LEGEND



REFERS TO THE APPROPRIATE S.E.S.C. KEYING SYSTEM DETAIL (SEE THIS SHEET C4.0)

NRCS SOIL BOUNDARY EASEMENT AREA

SOIL EROSION CONTROL SCHEDULE

THIS NARRATIVE IS TO ACCOMPANY THE EROSION AND SEDIMENTATION CONTROL PLAN FOR THE BABCOCK DRAIN PREPARED BY LSG ENGINEERS & SURVEYORS OF LANSING, MICHIGAN, AND SHALL BE CONSIDERED A PART OF THE EROSION AND SEDIMENTATION CONTROL PLAN.

THE PROJECT SITE IS LOCATED IN SECTION 9, T9N, R4E, MAPLE GROVE TOWNSHIP, SAGINAW COUNTY, MICHIGAN. I. GENERAL STATEMENT OF THE PROJECT

- A. THE PROPOSED IMPROVEMENTS INCLUDE THE CONSTRUCTION OF AN OPEN CHANNEL BRANCH TO THE BABCOCK DRAIN.
- B. THE AREAS OF PROPOSED EARTH DISTURBANCE ARE SHOWN ON THE
- SOIL EROSION CONTROL PLAN. C. THE STORM WATER MANAGEMENT FACILITIES WILL CONSIST OF OPEN
- CHANNEL DRAIN WITH RIP-RAP, BANK SLOPE PROTECTION, AND APPURTENANT CULVERTS. D. THE STORM WATER CALCULATIONS FOR THE SITE WERE PREPARED IN ACCORDANCE WITH THE SAGINAW COUNTY PUBLIC WORKS
- COMMISSIONER'S STANDARDS. ACCELERATED EROSION AND SEDIMENTATION SHALL BE LIMITED BY THE STABILIZATION OF DISTURBED AREAS AS SOON AS POSSIBLE. IN ADDITION, LIMITS OF EARTHMOVING HAVE BEEN IDENTIFIED FOR EACH PHASE OF THE SOIL EROSION CONTROL PLAN. THE CONTRACTOR SHALL NOTE THE SCHEDULE FOR EARTHMOVING AND INTERIM
- F. ALL DISTURBED AREAS INTENDED TO BE LAWN OR GRASS AREAS SHALL. IMMEDIATELY AFTER FINAL GRADING, BE SEEDED PER THE PERMANENT STABILIZATION MIX AND MAINTAINED.

STABILIZATION AND THE RESTRICTIONS IMPOSED ON STARTING THE

- G. CONSTRUCTION ON THIS PROJECT SHOULD BEGIN IN SUMMER OF
- TOPOGRAPHIC FEATURES OF THE PROJECT AREA THE LOCATION OF THE SITE, CONTOURS, PROPERTY LINES, ACREAGE AND ALL OTHER PHYSICAL FEATURES WERE LOCATED BY THE USE OF GROUND OBSERVATION AND ARE SHOWN ON THE PLAN.
- III. TYPES, DEPTH, SLOPE AND AREAL EXTENT OF SOILS. THE ENTIRE SITE IS MADE UP OF BELLEVILLE FINE SAND, PARKHILL LOAM (0 TO 1 PERCENT SLOPES), SELFRIDGE LOAMY SAND (0 TO 3 PERCENT SLOPES), COVERT SAND (1 TO 6 PERCENT SLOPES).
- IV. PROPOSED ALTERATION TO THE AREA

ALL PROPOSED ALTERATIONS ARE SHOWN ON THE PLAN. PROPOSED GRADES HAVE BEEN SELECTED KEEPING IN MIND THE EXISTING DRAINAGE PATTERNS. THE GRADING PLAN WILL INDICATE THE FINAL GRADES OF THE SITE.

AMOUNT OF RUNOFF FROM THE PROJECT AREA AND THE UPSTREAM WATERSHED

THE AMOUNTS OF RUNOFF FROM THE PROJECT AREA OR FROM THE UPSTREAM WATERSHED WILL BE KEPT TO A MINIMUM BY THE USE OF SOIL EROSION CONTROL MEASURES.

VI. STAGING OF EARTHMOVING ACTIVITIES

SEE TABLE BELOW:

NEXT PHASE.

VII. TEMPORARY CONTROL MEASURES AND FACILITIES FOR USE DURING EARTHMOVING

STOCKPILES SHALL BE USED TO CONTAIN ALL STRIPPED TOPSOIL IN A LIMITED AREA IN ORDER TO KEEP THE DISTURBED AREA TO A MINIMUM. STOCKPILES THAT WILL EXIST BETWEEN 20 DAYS AND 12 MONTHS SHALL BE STABILIZED WITH A TEMPORARY COVER CROP OF GRASS AS SET FORTH IN THE INTERIM STABILIZATION GUIDELINES.

B. STABILIZED CONSTRUCTION ENTRANCES: THIS ENTRANCE PROTECTION FACILITY SHALL BE USED TO KEEP STORMWATER FROM FLOWING UNCHECKED FOR THE SITE AND TO

COLLECT SEDIMENT OFF THE CONSTRUCTION VEHICLES.

C. TEMPORARY SEEDING: SEE TEMPORARY SEEDING AS NOTED ON THE PLANS.

VIII. PERMANENT CONTROL MEASURES AND FACILITIES FOR LONG-TERM PROTECTION

- A. PERMANENT STABILIZATION OR PERMANENT SEEDING: SEE PERMANENT STABILIZATION AS NOTED ON PLANS.
- HAY OR STRAW MULCH SHALL BE APPLIED TO SEEDING AREAS TO HELP ESTABLISH A PERMANENT GRASS COVER AND TO PREVENT EROSION. IT SHALL BE APPLIED AT THE RATE OF 3 TONS PER
- C. EROSION CONTROL BLANKETS OR FABRIC: WHERE SPECIFIED BY THE ENGINEER IN AREAS WHERE THE SLOPE EXCEEDS 3H:1V, NORTH AMERICAN GREEN S75 SOIL EROSION CONTROL BLANKET SHALL BE INSTALLED TO PREVENT EROSION.
- WHERE DIRECTED BY THE ENGINEER IN AREAS WHERE STABILIZATION IS FOUND TO BE DIFFICULT, THE ENGINEER MAY DIRECT THE CONTRACTOR TO INSTALL SOD. SOD MATERIAL, PLACEMENT AND STAKING SHALL CONFORM TO THE GUIDELINE SPECIFICATIONS FOR SODDING BY THE AMERICAN SOD PRODUCERS ASSOCIATION.
- E. PERMANENT STABILIZATION ENERGY DISSIPATERS OR ROCK RIPRAP SEE PERMANENT STABILIZATION AS NOTED IN THE PLANS. ROCK RIPRAP SLOPE PROTECTION INVOLVES THE PLACEMENT OF ROCK RIPRAP ON GEOTECHNICAL FABRIC.
- IX. MAINTENANCE PROGRAM FOR THE CONTROL FACILITIES INCLUDING DISPOSAL OF MATERIALS REMOVED FROM THE CONTROL FACILITIES.
- A. ALL SEDIMENT AND EROSION CONTROL FACILITIES SHALL BE CHECKED FOR DAMAGE AFTER EACH STORM. ALL FACILITIES THAT ARE DAMAGED, CLOGGED OR CAN NO LONGER PERFORM THE FILTRATION OR SEDIMENTATION OF SUSPENDED SOILS SHALL BE REPLACED.
- B. ANY PERMANENT SEEDED AREAS THAT BECOME ERODED SHALL HAVE THE TOPSOIL REPLACED, THE GRASS SEED RESOWN AND MULCH REAPPLIED, OR AT THE DIRECTION OF THE OWNER, SOD MAY BE

X. EQUITABLE OWNER/DEVELOPER/RESPONSIBLE PARTY

BRIAN J. WENDLING SAGINAW COUNTY PUBLIC WORKS COMMISSIONER 111 S. MICHIGAN AVENUE SAGINAW, MICHIGAN

PHONE: (989) 790-5258

ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 20 DAYS MUST BE STABILIZED IMMEDIATELY. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE RECOMMENDED RATES DISTURBED AREAS WHICH AR NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MAY BE STABILIZED IN ACCORDANCE WITH TEMPORARY SEEDING SPECIFICATIONS. DISTURBED AREAS WHICH ARE EITHER AT FINISHED GRADE OR WILL NOT BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

	DSTURBANCE/MEASURE		COMPLETE	MAY	JUN.	JUL.	AUG.	SEPT.	ост.
D3 TORBANGE/ MEASURE		START		2022	2022	2022	2022	2022	2022
1	1 INSTALL BMP'S.								
2	CONSTRUCTION ACTIVITIES.								
2.1	BEGIN INSTALLATION/CONSTRUCTION OF THE DOWNSTREAM END OF THE PROJECT.								
2.2	EXCAVATE CHANNEL AND INSTALL RIP RAP.								
2.3	INSTALL PIPING WORKING UPSTREAM.								
2.4	ROUGH GRADE AND FINAL GRADE AS WORK PROCEEDS.								
3	REMOVE SEDIMENT, FINAL GRADE AND SEED.								
4	FINISH STABILIZATION.								
5	REMOVE TEMPORARY CONTROL MEASURES.								

CONTRACTOR SHALL PROVIDE A DETAILED CONSTRUCTION SEQUENCE BASED ON CONTRACT DATES. THE CONSTRUCTION SEQUENCE SCHEDULE SHALL BE INCORPORATED INTO PLANS ISSUED FOR CONSTRUCTION

EACH WORK AREA SHALL BE FULLY RESTORED AND READY FOR PERMANENT SESC MEASURES BEFORE CONTRACTOR CAN COMMENCE WORK AT OTHER AREAS. PERMANENT SESC MEASURES SHALL BE COMPLETED WITHIN 5 CALENDAR DAYS.

MISS Know what's below. Call before you dig. EGLE PERMIT NO.

WRP 026900 v.1

CHECKED BY ADB DATE ____JAN. 11, 2021 ROJECT NO. 2409

Engineers

& Surveyors

3135 PINE TREE ROAD


SUITE D

LANSING, MI 48911

PH. (517) 393-2902

FAX (517) 393-2608

www.lsg-es.com



FROSION CONTROL MEASURES

_									
	KEY	SESC MEASURE	SYMBOL	WHERE USED					
T/P	1	SEEDING	Manual Control of the	When bare soil is exposed, temporarily or permanently, to erosive forces from wind and or water on flat areas, mild slopes, grassed waterways and spillways, diversion ditches and dikes, borrow and stockpile areas, and spoil piles.					
* T	2A	MULCH BLANKETS		On exposed slopes, newly seeded areas, new ditch bottoms, or areas subject to erosion. * The MDMB keying system was used for this erosion control measure.					
Р	7	RIPRAP		Along drain banks shorelines, or where concentrated flows occur. slows velocity, reduces erosion and sediment load.					
Т	26	DUST CONTROL		As a temporary measure on exposed and unstabilized areas that must be protected from wind or water erosion.					
Т	40	CHECK DAM	200 CO	In constructed and existing flow corridors to reduce flow velocities.					

*PLACE AS DIRECTED BY THE ENGINEER

CEDIMENT CONTDOL MEACHDEC


_		SEDIMEN	I CONTR	OL MEASURES
	KEY	SESC MEASURE	SYMBOL	WHERE USED
Т	66	STABILIZED CONSTRUCTION ACCESS		At locations where construction equipment will enter and exit the drain easement and tracking of soil is anticipated.

CONSTRUCTION & RESTORATION ACTIVITY DETAILS

KEY	BEST MANAGEMENT PRACTICE	SESC PLAN REQUIRED
111	Cross-Vanes	ALWAYS
т		Г


DENOTES TEMPORARY SESC MEASURES

P - DENOTES PERMANENT SESC MEASURES



CLAY BOTTOM DETAIL E

STA. 23+86 TO STA. 24+36 C4.1



WET SLOPE LINING SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.


2. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.

EROSION BLANKETS &


TURF REINFORCEMENT

MATS SLOPE INSTALLATION (B) 1994 JOHN McCULLAH

USE WHERE DIRECTED BY ENGINEER.




TOPSOILING



SEEDING & MULCHING





PROPOSED CHANNEL DETAIL

		SEE	DING			
		TEMF	PORARY			
SEED MIX	SEASONAL LIMITATIONS	APPLICATION RA	ATE, LBS PER ACRE	- SPEC	CIES	% BY WEIGH
CEREAL RYE	MAR 15 TO OCT 15	15	70	CEREAL	L RYE	100
		PERM	MANENT			
SEED MIX	SEASONAL LIMITATIONS	APPLICATION RA	ATE, LBS PER ACRE	- SPEC	CIES	% BY WEIGH
ROADSIDE R.O.W. (MDOT, TUF)	MAR 15 TO JUN 1 -OR- AUG 1 TO OCT 15	45	220	CREEPING RED FESCUE PERENNIAL RYEGRASS HARD FESCUE KENTUCKY BLUEGRASS FULTS SALT GRASS		40 20 20 10
RESIDENTIAL/ COMMERCIAL LAWN (MDOT, THM)		45	220	KENTUCKY BLUEGRASS PERENNIAL RYEGRASS CREEPING RED FESCUE		30 20 50
GRASSED WATERWAY (GW)		6	30	TALL FI PERENNIAL ANNUAL R OTH	RYEGRASS	60 24 13 3
UPLANDS (MDOT, ES)		11	54	TIMOTHY PERENNIAL RYEGRASS BIG BLUESTEM SWITCHGRASS INDIANGRASS LITTLE BLUESTEM		44 20 17 7 6 6
WETLANDS, ETC.			N SHEET CX.X, 37 "SEEDING OF	AND NATIVE PLANTS	S" IN PROJECT	MANUAL.
		SUPP	LEMENTS			
ITEM	DESCRIPTI	ION	100	APPLICATION F		R ACRE
FERTILIZER	12-12-1	12		30	400	

MULCH

APPLICATION RATES AND PERCENT BY WEIGHT ARE BASED ON AMOUNT OF PURE LIVE SEED (PLS).

AT THE DISCRETION OF THE ENGINEER, DORMANT SEEDING MAY BE MADE IN LATE FALL TO GERMINATE IN SPRING. DORMANT SEEDINGS MUST BE MULCHED. DOWNOT SEED WHEN GROUND IS FROZEN OR SNOW COVERED. DO NOT USE DORMANT SEEDING ON GRASSED WATERWAYS.

1,200

HAY OR STRAW

EGLE PERMIT NO. WRP 026900 v.1

6,000

Engineers

& Surveyors

3135 PINE TREE ROAD SUITE D LANSING, MI 48911 PH. (517) 393-2902

FAX (517) 393-2608 www.lsg-es.com

EROSION CONTROL FOR


MISS Know what's below.


HOR. N/A VERT. N/A Call before you dig.

DESIGNED BY ADB DRAWN BY ____AJI_ CHECKED BY ADB DATE ____JAN. 11, 2021 PROJECT NO.

2409

C4.1





TYPICAL SIGN ASSEMBLIES (5.0)

Know what's **below.**Call before you dig.

SCALE HOR. <u>1" = 1000'</u> VERT. N/A PROJECT NO.

EGLE PERMIT NO. WRP 026900 v.1

Engineers & Surveyors

3135 PINE TREE ROAD SUITE D LANSING, MI 48911 PH. (517) 393-2902 FAX (517) 393-2608 www.lsg-es.com

DESIGNED BY GKL

DRAWN BY GKL

CHECKED BY ADB

DATE MARCH 18, 2022

2409

C5.0