



Brian J. Wendling
Public Works Commissioner
Governmental Center
111 S. Michigan Ave., Suite 103
Saginaw, MI 48602
Phone 989-790-5258
Fax 989-790-5259

SAGINAW COUNTY PUBLIC WORKS COMMISSIONER

PARKER SWAMP DRAIN

NOTICE OF LETTING

NOTICE OF LETTING

DATE: June 9, 2022
TIME: 10:00 a.m.
LOCATION: Spicer Group, Inc.
230 S. Washington Avenue
Saginaw, MI 48607

QUESTIONS: (989) 233-0136

The Saginaw County Public Works Commissioner will meet on the above date, time, and location to receive construction bids for the Parker Swamp Drain. Bids will then be opened and publicly announced.

The Parker Swamp Drain will be let in 1 section as follows, having the length, average depth and width as set forth:

Said Drain is an open channel, approximately 3.0 miles in length, and has an average depth of 7 feet and an average bottom width of 4 feet. This Notice of Letting, the plans, specifications, and bid proposal shall be considered a part of the contract. The following items will be required, and a contract let for same:

PARKER SWAMP DRAIN AND BRANCH

OPEN CHANNEL CONSTRUCTION

3,894	Lin. Ft.	Drain Restoration
8,324	Lin. Ft.	Open Channel Excavation
3,011	Lin. Ft.	Channel Cleanout
8,463	Lin. Ft.	Spoil Leveling
2,872	Lin. Ft.	Spoil Hauling
1	Lump Sum	Site Clearing

CROSSINGS PARKER SWAMP DRAIN

No. 2 Station 24+30 - Sprague. - Native Drive

1	Lump Sum	Remove Existing Crossing
---	----------	--------------------------

No. 2A Station 32+95 - SpraguTrepkowski, P. & E., Bakos, J. & T. - Native Drive

1	Lump Sum	Remove Existing Crossing
---	----------	--------------------------

No. 3 Station 34+58 - Hillbridge Road - SCRC - Bituminous Road

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

No. 3A Station 41+50+ - Stevens, K.

1	Lump Sum	Rockford Crossing
---	----------	-------------------

No. 4 Station 49+04 - Mielke Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

No. 5 Station 56+71 - Mills, G. & L. - Native Drive

62 Lin. Ft. 87" x 63" C.M.P.A., (3" x 1" Corr., 12 Ga.)

No. 6 Station 59+23 - Dobulis, I. & M. - Bituminous Drive

1 Lump Sum Cleanout Existing Crossing

No. 7 Station 59+77 - Labean, R. - Native Drive

1 Lump Sum Remove Existing Crossing

No. 8 Station 68+38 - Wilkinson Road. -Bituminous Road

1 Lump Sum Cleanout Existing Crossing

No. 9 Station 82+73 - Frank, G. & R. - Native Drive

60 Lin. Ft. 42" Dia. Stm. Swr.

No. 9A Station 89+31 - Consumers Energy - Native Drive

30 Lin. Ft. 57" x 38" C.M.P.A. (2 2/3" x 1/2 " Corr., 12 Ga.)

No. 10 Station 94+26 - Munger, R. & C. - Gravel Drive

50 Lin. Ft. 36" Dia. Stm. Swr.

No. 10A Station 97+85 - SCRC - Pierce Road, Bituminous

50 Lin. Ft. 15" Dia. Stm. Swr.

No. 11 Station 99+12 - Munger, R. & C. - Gravel Drive

50 Lin. Ft. 36" Dia. Stm. Swr.

No. 11A Station 100+10 -SCRC - Pierce Road, Bituminous

50 Lin. Ft. 15" Dia. Stm. Swr.

No. 11B Station 102+75 -SCRC - Pierce Road, Bituminous

50 Lin. Ft. 15" Dia. Stm. Swr.

No. 12 Station 107+08 - SCRC - N. Gleaner & Pierce Roads, Bituminous

64 Lin. Ft. 36" Dia. C76-III R.C.P.

50 Lin. Ft. 15" Dia. Stm. Swr.

40 Lin. Ft. 15" Dia. Stm. Swr.

1 Each 6' Dia. M.H.

BRANCH NO. 1 OF THE PARKER SWAMP DRAIN

CROSSINGS

No. 15 Station 1+33 - Frank, G. & R.- Native Drive

60 Lin. Ft. 42" Dia. Stm. Swr.

No. 16 Station 5+82 - Frank, G. & R. - Wood Footbridge

1 Lump Sum Cleanout Under Existing Footbridge

No. 17 Station 11+14 - Munger, R. - Native Drive

50 Lin. Ft. 42" Dia. Stm. Swr.

No. 17A Station 14+90 - SCRC - Pierce Road, Bituminous

50 Lin. Ft. 15" Dia. Stm. Swr.

No. 17B Station 16+00 - SCRC - Pierce Road, Bituminous

50 Lin. Ft. 18" Dia. Stm. Swr.

No. 18 Station 23+94 -SCRC - Mielke Road - Bituminous Road

60 Lin. Ft. 36" Dia. Stm. Swr.

1 Each 7' Dia. M. H.

40	Lin. Ft.	15" Dia. Stm. Swr.
<u>No. 19 Station 24+49 - SCRC - Pierce Road - Bituminous Road</u>		
50	Lin. Ft.	36" Dia. Stm. Swr.
<u>No. 20 Station 26+78 - Wirtz, J. - Gravel Drive</u>		
50	Lin. Ft.	36" Dia. Stm. Swr.
<u>No. 21 Station 28+16 - Wirtz, J. - Gravel Drive</u>		
100	Lin. Ft.	36" Dia. Stm. Swr.
<u>No. 22 Station 34+72 - Hughes, J. & L. -Native Drive</u>		
50	Lin. Ft.	30" Dia. Stm. Swr.
<u>No. 23 Station 38+25 - Cassells, M & M. - Gravel Drive</u>		
1	Lump Sum	Cleanout Existing Structure
<u>No. 24 Station 40+98 - Datte, K. & S. Trust - Gravel Drive</u>		
1	Lump Sum	Cleanout Existing Structure
<u>No. 25 Station 43+01 - Pfahl, T. & S. - Gravel Drive</u>		
1	Lump Sum	Cleanout Existing Crossing

MAINTENANCE LANE CULVERTS

40	Lin. Ft.	15" Dia. Stm. Swr.
40	Lin. Ft.	24" Dia. Stm. Swr.
40	Lin. Ft.	30" Dia. Stm. Swr.
40	Lin. Ft.	24" Dia. Stm. Swr.

SOIL EROSION AND SEDIMENT CONTROL

500	Sq. Yds.	Miscellaneous Plain Riprap
50	Lin. Ft.	Grass Spillway
150	Lin. Ft.	Plain Riprap Spillway
2,850	Lin. Ft.	Plain Riprap Toe of Slope Protection
1,500	Sq. Yd.	NAG C-350 Erosion Control Blanket (or approved equal)
12	Each	35' of 15" C.M.P. Surface Outlet Tube
4	Each	35' of 18" C.M.P. Surface Outlet Tube
5	Each	10" and Larger Tile Outlet Repair
15	Each	6" to 8" Tile Outlet Repair
40	Each	4" to and Smaller Tile Outlet Repair
80	Each	Plain Riprap Splash Pad

MISCELLANEOUS ITEMS

1	Lump Sum	Cleanup and Restoration
1	Lump Sum	Seeding, Fertilizing, and Mulching
1	Lump Sum	Traffic Control - County Roads

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at the Saginaw County Public Works Commissioner's Office and available to interested parties. Bidding Documents, including plans and specifications, may be examined, beginning May 16, 2022 at the following:

Online at <http://www.saginawcounty.com/PublicWorks/Current-Projects.aspx>

Hard copies of the Contract Documents may be obtained upon payment of a \$100 non-refundable fee, beginning on May 19, 2022. An additional **non-refundable** charge of \$10.00 will be required for mailing out Bidding Documents. To order hard copies of the Contract Documents, please contact Ms. Angie


McCullen at Spicer Group at (989) 921-5538.

A security deposit in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

A **mandatory pre-bid conference** will be held at **10:00 a.m.** on the **19th day of May 2022** at the office of Spicer Group, Inc., 230 S. Washington Avenue, Saginaw, Michigan 48607. It is a requirement that any prospective General Contractor bidding attend this meeting. Representatives of the Owner and Professional will be present to discuss the project. Attendance is required for sealed bids to be accepted. The Professional will transmit to all prospective bidders of record an Addendum as the Professional considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be legally effective.

The Contract will be awarded to the lowest responsive and responsible bidder giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

Dated: May 16, 2022



Brian J. Wendling
Saginaw County Public Works Commissioner